

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
840	(142 & 143) RS-6	WILL	17	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% FED.	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
				1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	179	179				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	70	70				
40600300	AGGREGATE (PRIME COAT)	TON	344	344				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	27	27				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	125	125				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	7200	7200				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	85578	85578				
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SO YD	1027	1027				
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SO YD	2568	2568				
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SO YD	1540	1540				
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SO YD	1500	1500				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	682	682				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	71043	71043				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	78700	78700				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	23681	23681				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	78700	78700				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1326	1326				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1030	1030				
* X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3380	3380				
XX003560	CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	495	495				
20076600	TRAINEES	HOUR	1000	1000				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES				

© Y080
• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

1/8/2009 10:58:10 AM C:\PLOT\100101.DWG