

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
OR37	2004-076 RS	COOK	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5	5					
40600300	AGGREGATE (PRIME COAT)	TON	25	25					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	4					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	252	252					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	258	258					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1070	1070					
42001300	PROTECTIVE COAT	SO YD	19	19					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	12738	12738					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	557	557					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	1537	1537					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	354	354					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	232	232					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	951	951					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10					
60404940	FRAMES AND GRATES, TYPE 23	EACH	12	12					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	396	396					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4351	4351					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	502	502					

SUMMARY OF QUANTITIES			URBAN 100% FED.		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	24	24					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	132	132					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4351	4351					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	502	502					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	24	24					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	125	125					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	113	113					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	320	320					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	502	502					
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	6	6					

1/12/2009 8:48:51 AM \\P090481801\pub_cdm\cdo

* Specialty Items

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES
NAME	DATE	