F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

100% FEDERAL

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION CODE I 000 ROADWAY	SFTY-1B SIDEWALKS	Y060 WATER MAINS	Y079 HAZARD WASTE REMEDIATION ITEMS
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	200	200			
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	175	175			
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	53	53			
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	118	118			
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	191	191			
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	234	234			
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	51	51			
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	116	116			
550A2360	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 24"	FOOT	631	631			
550A2380	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 30"	FOOT	10	10			
550A2530	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 15"	FOOT	135	135			
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	210	210			
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	175	175			
550A2620	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 48"	FOOT	92	92			
55100500	STORM SEWER REMOVAL 12"	FOOT	749	749			
55100900	STORM SEWER REMOVAL 18"	FOOT	60	60			
56106300	ADJUSTING WATER MAIN 6"	FOOT	154			154	
56300300	ADJUSTING WATER SERVICE LINES	FOOT	575			575	
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	5			5	
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	4			4	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	22	22			
60219500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME AND LID	EACH	7	7			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2			

* SPECIALITY ITEMS

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

REVISIONS	
NAME	DATE
IDOT	1-30-09

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY QUANTITIES

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT. HORIZ.
DATE: 11/05/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
3000 CLEAR LAKE AVENUE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL DESIGN FIRM NO. 184-000279
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 793-3945, (217) 793-3227 FAX E-MAIL: GAB@GREENEANDBRADFORD.COM

COMPUTER FILE NO. SUMMARYP2-4

PROJECT 03145
09/05/07-WCB