DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
681	(115)RS-1	LIVINGSTON	279	38
STA.	173+00	TO STA.	178+00	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66375

N

0 20 40

SCALE IN FEET

1. STA. 173+39.38, 21.26' LT.
EXIST. INLET (18" DIA)
RIM = 680.80
FL (N-6") = 678.13
INV. = 676.22
REMOVING INLETS TO MAINATAIN FLOWS

2. STA. 173+83.93, 21.35' LT.
EXIST. INLET (18" DIA)
RIM = 680.87
FL (N-6") = 678.77
INV. = 676.57
REMOVING INLETS TO MAINATAIN FLOWS

3. STA. 174+47.98, 24.51' RT.
EXIST. INLET (24" DIA)
RIM = 680.16
FL (W-10") = 679.30
INV. = 676.31
TBR

4. STA. 174+94.95, 22.86' RT.
EXIST. INLET (24" DIA)
RIM = 680.67
FL (E-10") = 679.05
FL (W-12") = 679.05
INV. = 676.92
TBR

5. EXISTING 24" CMP
USFL = 678.59
DSFL = 678.77
TBR

6. STA. 175+71.24
25.17' RT.
REMOVAL OF EXISTING STRUCTURES

STA. 58+81.91
MATCH EXISTING

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
27.3 SQ. YD.

AMERICO M. MANZO

AMERICO M. MANZO

MARVIN J & L.B. SATTERFIELD

CONCRETE PLANKS CROSSING

ALLIANCE GRAIN COMPANY

STA. 174+71.56 ℄ FAP 681
STA. 60+00.00 ℄ MAPLE ST.

SIDEWALK REMOVAL
195 SQ. FT.
PLANTER

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
173.3 SQ. YD.

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
173.3 SQ. YD.

TEMPORARY CONSTRUCTION EASEMENT

SIDEWALK REMOVAL
32 SQ. FT.

CURB REMOVAL
84 FOOT

PAVEMENT REMOVAL
6.9 SQ. YD.

PAVEMENT REMOVAL
36.7 SQ. YD.

PAVEMENT REMOVAL
7.3 SQ. YD.

32 FOOT ADJUSTING
6" WATER MAIN

℄ FAP RTE. 681
(IL RTE. 116)

STA. 173+00 MATCHLINE

STA. 178+00 MATCHLINE

MAPLE ST.

BLOL RR

DRIVEWAY PAVEMENT REMOVAL 44 SQ. YD.

25 FOOT ADJUSTING WATER SERVICE LINES

SIDEWALK REMOVAL
156 SQ. FT.

SIDEWALK REMOVAL
341 SQ. FT.

HAZEL G. ALLEN

RONALD E. & DIANE S. SHAPLAND

SIDEWALK REMOVAL
334 SQ. FT.

CONTROL BOX

DROP BOX

PAVEMENT REMOVAL
78.8 SQ. YD.

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
40.4 SQ. YD.

VILLAGE OF CULLOM

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT
23.9 SQ. YD.

STA. 61+26.06
MATCH EXISTING

LEGEND

SIDEWALK REMOVAL	
DRIVEWAY PAVEMENT REMOVAL	
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	
PAVEMENT REMOVAL	
STORM SEWER PATCHES	
EXISTING PIPE CULVERT REMOVAL	
TREE REMOVAL	
TO BE RELOCATED	REL
TO BE REMOVED	TBR
TO BE ADJUSTED	TBA

REVISIONS	
NAME	DATE
IDOT REV. - WCB	10/08
IDOT	1-30-09

ILLINOIS DEPARTMENT OF TRANSPORTATION

REMOVAL AND ADJUSTMENT PLAN

FAP 681 (IL RTE. 116)
SECTION (115)RS-1
LIVINGSTON COUNTY
VILLAGE OF CULLOM

SCALE: VERT.
HORIZ.
DATE: 06/30/03

DRAWN BY: JAMESON
DESIGNED BY: BOTT
CHECKED BY: COLBROOK

GREENE & BRADFORD, INC. OF SPRINGFIELD
CONSULTING ENGINEERS
200 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
PROFESSIONAL ENGINEERING CORPORATION
PROFESSIONAL & STRUCTURAL ENGINEERING CORPORATION
(217) 793-8494, (217) 793-3227 (FAX) e-mail: — coordinator@gb-corp.com

COMPUTER FILE NO.
REMOVAL116BP2-01

PROJECT: 03145
09/05/07-WCB

IDOTPL-20 1"=20' 8/07/00

REMOVAL AND ADJUSTMENT PLAN - FAP 681 (IL RTE. 116) LIVINGSTON COUNTY