

SUMMARY OF QUANTITIES			100% FED
CODE NO.	CONSTRUCTION CODE TYPE:		I000 TOTAL QUANTITY
	ITEM	UNIT	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	258
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13.4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	80
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	80
40600990	TEMPORARY RAMP	SQ YD	28
44200630	CLASS A PATCHES, TYPE II, 15 INCH	SQ YD	183
44200631	CLASS A PATCHES, TYPE III, 15 INCH	SQ YD	75
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	7
44213000	PATCHING REINFORCEMENT	SQ YD	258
44213200	SAW CUTS	FOOT	1536
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3330
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	66566
70300635	TEMPORARY PAINT PAVEMENT MARKING LINE 6"	FOOT	8322
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	27459
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	66566
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	8322
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	823
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	10
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	833
X0322729	MATERIAL TRANSFER DEVICE	TON	3758
X0325536	RAPID SETTING POLYMER MODIFIED EMULSION	GALLON	16999
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
X0326129	ULTRA-THIN <sup>HOT-MIX ASPHALT</sup> SURFACE COURSE	SQ YD	89467
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	258
Z0075300	TIE BARS	EACH	276

\*SPECIALTY ITEMS

FILE NAME =	USER NAME = verdinam1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pwwork\pawelc\verdina\1\0106568\0366986-sh1-cover.dgn	PLDT SCALE = 50.0000' / IN.	DRAWN -	REVISED -			80	(32-2)RS-4	GRUNDY	8	3
PLDT DATE = Jan 30, 2009 - 02:18:21 PM	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 66906				
	DATE -	REVISED -	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT