

RESURFACING SCHEDULE														
LOCATION		LENGTH	PVMT AREA	HMA SURF CSE	LEVEL BINDER (MM)	HMA SURF REM 3/4"	HMA SURF REM (BUTT JT)	TEMP RAMP	BIT MAT (PR CT)	AGG (PR CT)	MIX FOR CRACKS, JOINTS & FLGWYS	LEVEL BINDER (HM)	HMA SHLD	AGG SHLD
STA TO STA		FOOT	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	TON	TON
PUTNAM COUNTY														
3+17.3 TO 377.3	BUTT JOINT	60	173.3	14.6	7.3	86.7	86.7	14.4	36	0.7	0.1	0.1		3.4
3+77.3 TO 109+28.5		10551.2	30481.2	2560.4	1280.2	30481.2			6401	121.9	9.1	15.2		600.8
SUBTOTAL				2575.0	1287.5	30567.9	86.7	14.4	6437	122.6	9.2	15.3	0.0	604.2
LASALLE COUNTY														
109+28.5 TO 140+02 BK		3073.5	8879.0	745.8	372.9	8879.0			1865	35.5	2.7	4.4		175
140+00 AH TO 154+98 BK		1498	4993.3	419.4	209.7	4993.3			1049	20.0	1.5	2.5		85.3
154+96 AH TO 328+81		17385	50325.6	4227.4	2113.7	50325.6			10568	201.3	15.1	25.2		990
328+81 TO 331+55		274	791.6	66.5	33.2	1278.7			166	3.2	0.2	0.4	61.4	10.4
331+55 TO 332+15	BUTT JOINT	60	173.3	14.6	7.3	140.0	140.0	14.4	36	0.7	0.1	0.1	13.4	2.3
332+15 TO 363+70	PAVING OMISSION	3155												
363+70 TO 364+30	BUTT JOINT	60	173.3	14.6	7.3	140.0	140.0	14.4	36	0.7	0.1	0.1	13.4	2.3
364+30 TO 368+08		378	1092.0	91.7	45.9	1764.0			229	4.4	0.3	0.9	84.7	14.4
368+08 TO 373+08		500	1888.7	158.7	79.3	2333.3			397	7.6	0.6	1.2	56.0	19
373+08 TO 377+09		401	1158.4	97.3	48.7	1871.3								
377+09 TO 377+69	BUTT JOINT	60	173.3	14.6	7.3	86.7	86.7	14.4	36	0.7	0.1	0.1		2.3
SUBTOTAL				5850.6	2925.3	71811.9	366.7	43.2	14382	274.1	20.7	34.9	228.9	1301.0
TOTAL				8425.6	4212.8	102379.8	453.4	57.6	20819	396.7	29.9	50.2	228.9	1905.2

PAVEMENT MARKING SCHEDULE											
LOCATION	LENGTH	URETHANE PVMT MARK-LINE 4"		URETHANE PVMT MARK-LINE 6"	URETHANE PVMT MARK-LINE 8"	URETHANE PVMT MARK-LINE 12"	URETHANE PVMT MARK-LINE 24"	URETHANE PVMT MARK-LET & SYMB, SPL	PRISMATIC CURB REFLECTORS	RAISED REFLECT PVMT MARK REMOVAL	RAISED REFLECT PVMT MARK
		WHITE	YELLOW	YELLOW	WHITE	WHITE	WHITE	WHITE	SQ FT	EACH	EACH
STA TO STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT				
PUTNAM COUNTY											
3+17.3 TO 109+28.5	10611.2	21222		2566						133	133
NO PASSING ZONE:											
9+22 TO 21+23 EBL			1201								
18+44 TO 25+56 WBL			712								
41+44 TO 51+80 EBL			1036								
51+80 TO 58+99 WBL			719								
68+18 TO 77+56 EBL			938								
78+22 TO 86+29 WBL			807								
92+91 TO 101+71 EBL			880								
100+43 TO 109+28.5 WBL			886								
PUTNAM SUBTOTAL		21222	7179	2566	0	0	0	0	0	133	133
LASALLE COUNTY											
109+28.5 TO 140+02 BK	3073.5	6147		768						38	38
140+00 AH TO 154+98 BK	1498	2996		375						19	19
154+96 AH TO 328+81	17385	34770		4346						217	217
328+81 TO 330+00	10119	20238		2530						126	126
330+00 TO 373+08	4308	8127	7145	170	1086	152	68	140.4	46	13	13
373+08 TO 377+69	461	922	20	115	332	152	68		16	5.8	5.8
LASALLE SUBTOTAL		73200	10376	8304	1418	304	136	140.4	62	419	419
PROJECT TOTAL		47455.7	111977	10870	1418	304	136	140.4	62	552	552