

MAINLINE SCHEDULE

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/4"		TEMPORARY RAMP		POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE MATERIALS (PRIME COAT)		MIXTURE FOR CRACK, JOINTS & FLANGEWAYS		LEVELING BINDER (HM) N70		LEVELING BINDER (MM) N70		HOT-MIX ASPHALT SURFACE CSE. MIX "D" N70	
	SQ YD		SQ YD		GAL		TON		TON		TON		TON		TON	
	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT	LT	RT
STA. 0+00 TO STA. 5+00	194	194	12	39	35	35	1	1	0.1	0.1	0.1	0.1	8	8	16	16
STA. 5+00 TO STA. 10+00	805	771		104	145	139	2	2	0.2	0.2	0.4	0.4	34	32	68	65
STA. 10+00 TO STA. 15+00	1066	1227	144		192	123	2	2	0.4	0.4	0.6	0.6	45	52	90	103
STA. 15+00 TO STA. 20+00	1616	1606	51	51	291	289	3	3	0.5	0.5	0.8	0.8	68	67	136	135
STA. 20+00 TO STA. 25+00	895	896	25	25	161	139	2	2	0.3	0.3	0.4	0.4	38	38	75	75
STA. 25+00 TO STA. 30+00	1377	1179	76	76	248	139	3	2	0.4	0.4	0.7	0.7	58	50	116	99
STA. 30+00 TO STA. 35+00	1428	1586	135	65	257	127	3	3	0.5	0.5	0.8	0.8	60	67	120	133
STA. 35+00 TO STA. 40+00	177	1044		198	32	188	1	2	0.3	0.3	0.3	0.5	7	44	15	88
STA. 40+00 TO STA. 45+00	613	571	130	12	110	103	1	1	0.3	0.3	0.3	0.3	26	24	51	48
SUBTOTAL	8171	9074	573	570	1471	1282	18	18	3	3	4.4	4.6	344	382	687	762
TOTAL	17245		1143		**2753		36		6		9		726		1449	

** QUANTITY OF THIS ITEM HAS BEEN INCLUDED TO "FOG COAT" THE LEVELING BINDER LIFT

RAISED REFLECTIVE PAVEMENT MARKING SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
STA. 0+00 TO STA. 5+00	1
STA. 5+00 TO STA. 9+50	7
STA. 9+50 TO STA. 10+00	1
STA. 10+00 TO STA. 15+00	21
STA. 15+00 TO STA. 20+00	6
STA. 20+00 TO STA. 25+00	1
STA. 25+00 TO STA. 30+00	3
STA. 30+00 TO STA. 35+00	15
STA. 35+00 TO STA. 35+70	8
STA. 35+70 TO STA. 40+00	6
STA. 40+00 TO STA. 45+00	
TOTAL	69

MAINLINE SCHEDULE

LOCATION	AGGREGATE WEDGE SHOULDERS TYPE B
	TON
	LT RT
STA. 0+00 TO STA. 5+00	40 32
STA. 5+00 TO STA. 10+00	142 111
STA. 10+00 TO STA. 15+00	101 142
STA. 15+00 TO STA. 20+00	105 104
STA. 20+00 TO STA. 25+00	98 98
STA. 25+00 TO STA. 30+00	116 122
STA. 30+00 TO STA. 35+00	87 94
STA. 35+00 TO STA. 40+00	142 89
STA. 40+00 TO STA. 45+00	98 126
SUBTOTAL	929 918
TOTAL	1847