

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22		FULTON	71	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 133RS-3;134RS-2;135RS-5				

# SCHEDULE OF QUANTITIES

7820100

TERMINAL MARKER - DIRECT APPLIED	UNIT
LOCATION	EACH
IL 78: RT Sta. 261+47.5	1
IL 78: LT Sta. 262+22.5	1
IL 78: RT Sta. 266+85	1
IL 78: LT Sta. 266+85	1
IL 78: RT Sta. 267+15.5	1
IL 78: LT Sta. 267+15.5	1
IL 78: RT Sta. 271+90.5	1
IL 78: LT Sta. 271+78	1
IL 78: LT Sta. 305+04.5	1
IL 78: RT Sta. 306+37.5	1
IL 78: LT Sta. 314+67	1
IL 78: RT Sta. 315+48	1
IL 78: LT Sta. 328+70	1
IL 78: RT Sta. 328+20	1
IL 78: LT Sta. 332+70	1
IL 78: RT Sta. 332+20	1
<b>TOTAL</b>	<b>16 EACH</b>

LR631020

TRAFFIC BARRIER TERMINAL, TYPE 1	UNIT
LOCATION	EACH
IL 78: RT Sta. 315+35 TO 315+48	1
<b>TOTAL</b>	<b>1 EACH</b>

X0301512

GUARDRAIL AGGREGATE EROSION CONTROL	UNIT
LOCATION	TON
IL 78: RT Sta. 261+47.5 TO 266+85	26.63
IL 78: LT Sta. 262+22.5 TO 266+85	22.91
IL 78: RT Sta. 267+15.5 TO 271+90.5	23.53
IL 78: LT Sta. 267+15.5 TO 271+78	22.91
IL 78: LT Sta. 305+04.5 TO 314+67	47.68
IL 78: RT Sta. 306+37.5 TO 315+48	46.45
IL 78: LT Sta. 328+70 TO 332+70	19.82
IL 78: RT Sta. 328+20 TO 332+20	19.82
<b>TOTAL</b>	<b>230 TON</b>

50104400

CONCRETE HEADWALL REMOVAL	UNIT
LOCATION	EACH
IL 78: RT Sta. 315+44 (NW CORNER AT DIVISION)	1
<b>TOTAL</b>	<b>1 EACH</b>

66700205

PERMANENT SURVEY MARKERS, TYPE I	UNIT
LOCATION	EACH
IL 78: Sta. 52+22	1
<b>TOTAL</b>	<b>1 EACH</b>

66700605

PERMANENT SURVEY TIES	UNIT
LOCATION	EACH
IL 78: Sta. 52+22	4
<b>TOTAL</b>	<b>4 EACH</b>

70300100

SHORT-TERM PAVEMENT MARKING (2 APPLICATIONS)	UNIT
LOCATION	FOOT
IL 78: Sta. 27+09 TO 174+00	2,938.2
IL 78: Sta. 175+00 TO 262+19	1,743.8
IL 78: Sta. 262+98 TO 351+60	1,772.4
IL 78: Sta. 102+24 TO 160+25	1,160.2
<b>TOTAL</b>	<b>7,615 FT</b>

70301000

WORK ZONE PAVEMENT MARKING REMOVAL	UNIT
LOCATION	FOOT
IL 78: Sta. 27+09 TO 174+00	489.7
IL 78: Sta. 175+00 TO 262+19	290.6
IL 78: Sta. 262+98 TO 351+60	295.4
IL 78: Sta. 102+24 TO 160+25	193.4
<b>TOTAL</b>	<b>1,269 FT</b>

78100100

RAISED REFLECTIVE PAVEMENT MARKER	UNIT
LOCATION	EACH
IL 78: Sta. 27+09 TO 174+00	184
IL 78: Sta. 175+00 TO 262+19	109
IL 78: Sta. 262+98 TO 351+60	111
IL 78: Sta. 102+24 TO 160+25	73
<b>TOTAL</b>	<b>477 EACH</b>

78300200

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	UNIT
LOCATION	EACH
IL 78: Sta. 27+09 TO 174+00	184
IL 78: Sta. 175+00 TO 262+19	109
IL 78: Sta. 262+98 TO 351+60	111
IL 78: Sta. 102+24 TO 160+25	73
<b>TOTAL</b>	<b>477 EACH</b>

48203029

HOT-MIX ASPHALT SHOULDERS, 8"	UNIT
LOCATION	SQ YD
IL 78: RT Sta. 239+30 TO 261+79	499.78
IL 78: RT Sta. 298+52 TO 314+86.50	363.22
IL 78: RT Sta. 315+63 TO 322+59	154.67
IL 78: LT Sta. 315+64 TO 322+73.50	157.67
IL 78: RT Sta. 323+41.50 TO 338+45	334.11
IL 78: LT Sta. 323+26 TO 351+59.84	629.74
IL 78: RT Sta. 339+55.50 TO 351+59.84	267.63
IL 78: RT Sta. 102+23.63 TO 123+75.70	478.24
IL 78: LT Sta. 102+23.63 TO 109+96.50	171.75
IL 78: LT Sta. 110+83.50 TO 123+76.30	287.29
IL 78: RT Sta. 124+40.30 TO 160+25	796.6
IL 78: LT Sta. 124+39.75 TO 160+25	796.72
<b>TOTAL</b>	<b>4,937 SQ YD</b>

70300220

TEMPORARY PAVEMENT MARKING - LINE 4"			
78005110			
EPOXY PAVEMENT MARKING - LINE 4"			
LOCATION	YELLOW SKIP FOOT	YELLOW SOLID FOOT	WHITE SOLID FOOT
IL 78: Sta. 27+09 TO 31+57	112		896
IL 78: Sta. 31+57 TO 36+71	129	514	1,028
IL 78: Sta. 36+71 TO 41+70	125	499	998
IL 78: Sta. 41+70 TO 46+83	128	513	1,026
IL 78: Sta. 46+83 TO 52+15	133		1,064
IL 78: Sta. 52+15 TO 57+32	129	517	1,034
IL 78: Sta. 57+32 TO 65+83	213	851	1,702
IL 78: Sta. 65+83 TO 73+26	186	743	1,486
IL 78: Sta. 73+26 TO 82+25	1	1,798	1,798
IL 78: Sta. 82+25 TO 91+48	231	923	1,846
IL 78: Sta. 91+48 TO 93+42	49	194	388
IL 78: Sta. 93+42 TO 100+42	175		1,400
IL 78: Sta. 100+42 TO 107+82	185	740	1,480
IL 78: Sta. 107+82 TO 174+00	1,655		13,236
STATION EQUATION			
IL 78: Sta. 175+00 TO 178+40	85		680
IL 78: Sta. 178+40 TO 185+48	177	708	1,416
IL 78: Sta. 185+48 TO 193+78	208	830	1,660
IL 78: Sta. 193+78 TO 241+76	1,200		9,596
IL 78: Sta. 241+76 TO 246+53	119	477	954
IL 78: Sta. 246+53 TO 259+07		2,508	2,508
IL 78: Sta. 259+07 TO 262+19	78	312	624
STATION EQUATION			
IL 78: Sta. 262+98 TO 269+86	172	688	1,376
IL 78: Sta. 269+86 TO 278+97	225	899	1,798
IL 78: Sta. 278+97 TO 342+70		12,746	12,746
IL 78: Sta. 342+70 TO 346+60	98	390	780
IL 78: Sta. 346+60 TO 351+60	125		1,000
STATION EQUATION			
IL 78: Sta. 109+24 TO 160+25	1,450		11,602
SUBTOTALS	7,388	26,850	76,122
<b>TOTAL</b>		<b>110,360 FT</b>	

	28000400	28000500	21400100	20400800	542D1087	54215577	28200200	28100825
	PERIMETER EROSION BARRIER	INLET & PIPE PROTECTION	GRADING & SHAPING DITCHES	FURNISHED EXCAVATION	PIPE CULVERTS, CLASS D, TYPE 2, 42"	METAL END SECTIONS, 42"	FILTER FABRIC	STONE DUMPED RIPRAP, CLASS B3
LOCATION	FOOT	EACH	FOOT	CU YD	FOOT	EACH	SQ YD	TON
IL 78: RT Sta. 315+44 (NW CORNER AT DIVISION ST.)	40	1	40	25	20	1	75	25
IL 78: RT Sta. 315+44 (SW CORNER AT DIVISION ST.)	40	1	40	25	20	1	75	25
<b>TOTAL</b>	<b>80 FT</b>	<b>2 EACH</b>	<b>80 FT</b>	<b>50 CU YD</b>	<b>40 FT</b>	<b>2 EACH</b>	<b>150 SQ YD</b>	<b>50 TON</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULE OF QUANTITIES

SCALE: VERT. DATE  
HORIZ. DATE

DRAWN BY  
CHECKED BY