

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	131RS-4	PEORIA	17	7
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

ENGINEER'S FIELD OFFICE TYPE B	
LOCATION	CAL MO
JOBSITE	2
TOTAL	2

EPOXY PAVEMENT MARKINGS					
LOCATION	4"	4"	8"	12"	24"
	YELLOW FEET	WHITE FEET	WHITE FEET	WHITE FEET	WHITE FEET
Sta. 1067+70 to 1226+80	13,999	31,820			
Route 8 Intersection	50	466	258	99	35
TOTAL	14,049	32,286	258	99	35

PERMANENT SURVEY MARKERS, TYPE 1	
LOCATION	EACH
CENTERLINE OF IL 78 AND IL 8 INTERSECTION	1
TOTAL	1

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TEMPORARY PAVEMENT MARKINGS					
LOCATION	4"	4"	8"	12"	24"
	YELLOW FEET	WHITE FEET	WHITE FEET	WHITE FEET	WHITE FEET
Sta. 1067+70 to 1226+80	13,999	31,820			
Route 8 Intersection	50	466	258	99	35
TOTAL	14,049	32,286	258	99	35

PERMANENT SURVEY TIES	
LOCATION	EACH
CENTERLINE OF IL 78 AND IL 8 INTERSECTION	4
TOTAL	4

TRAFFIC CONTROL & PROTECTION, STANDARD 701306	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

SHORT TERM PAVEMENT MARKING	
LOCATION	FEET
Sta. 1067+70 to 1226+80	1,580
Total	1,580
3 Application (Milled, Binder & Surface)	
3 x 1,580	4,740
TOTAL	4,740

CLASS D PATCHES 14 INCHES		
LOCATION	TYPE II	TYPE III
	SQYD	SQYD
BEGINING STA. 1067+70 TO SHISSLERS RD	397.3	0
SHISSLERS RD TO CLAYBAUGH RD	461.3	32.0
CLAYBAUGH RD TO ROSEBONM RD	216.0	64.0
ROSEBONM RD TO ENDING STA. 1226+80	432.0	0
TOTAL	1507.0	96.0

TRAFFIC CONTROL & PROTECTION, STANDARD 701336	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

RAISED REFLECTIVE PAVEMENT MARKERS	
LOCATION	EACH
1067+30 to 1226+80	200
TOTAL	200

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	1
TOTAL	1

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
Sta. 1067+70 - 1226+80	527
TOTAL	527

SCHEDULE OF QUANTITIES