

48101200 AGGREGATE SHOULDERS, TYPE B

	STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	SHOULDER THICKNESS (INCHES)	TON
	759+39.00		759+69.00	30.0	3.0	10.0	1.5	1.6
	759+69.00		765+84.00	BK 615.0	3.0	205.0	1.5	33.3
	00+00.00	AH	10+00.00	1000.0	3.0	333.3	1.5	54.2
	10+00.00		18+37.66	BK 837.7	3.0	279.2	1.5	45.4
	18+78.66	AH	28+52.00	973.3	3.0	324.4	1.5	52.7
	28+52.00		28+82.00	30.0	3.0	10.0	1.5	1.6
OMISSION	28+82.00		30+65.00	0.0	0.0	0.0	0.0	0.0
	30+65.00		30+95.00	30.0	3.0	10.0	1.5	1.6
	30+95.00		81+20.00	5025.0	3.0	1675.0	1.5	272.2
	81+20.00		82+94.00	174.0	3.0	58.0	1.5	9.4
	82+94.00		156+12.50	7318.5	3.0	2439.5	1.5	396.4
	156+12.50		156+42.50	30.0	3.0	10.0	1.5	1.6
OMISSION	156+42.50		157+15.00	0.0	0.0	0.0	0.0	0.0
	157+15.00		157+45.00	30.0	3.0	10.0	1.5	1.6
	157+45.00		294+11.50	13666.5	3.0	4555.5	1.5	740.3
	294+11.50		294+41.00	29.5	3.0	9.8	1.5	1.6
OMISSION	294+41.00		296+75.00	234.0	3.0	78.0	1.5	12.7
	296+75.00		297+05.00	30.0	3.0	10.0	1.5	1.6
	297+05.00		315+83.74	BK 1878.7	3.0	626.2	1.5	101.8
	316+00.00	AH	375+85.50	5985.5	3.0	1995.2	1.5	324.2
	375+85.50		461+22.00	8536.5	3.0	2845.5	1.5	462.4
	461+22.00		461+52.00	30.0	3.0	10.0	1.5	1.6
OMISSION	461+52.00		461+71.40	0.0	0.0	0.0	0.0	0.0
	461+71.40		462+01.40	30.0	3.0	10.0	1.5	1.6
	462+01.40		471+35.00	933.6	3.0	311.2	1.5	50.6
	471+35.00		473+76.00	241.0	3.0	80.3	1.5	13.1
OMISSION	473+76.00		477+41.00	0.0	0.0	0.0	0.0	0.0
	477+41.00		481+20.00	379.0	3.0	126.3	1.5	20.5
	481+20.00		482+06.78	BK 86.8	3.0	28.9	1.5	4.7
	482+17.54	AH	492+13.82	BK 996.3	3.0	332.1	1.5	54.0
	103+00.00	AH	116+58.50	1358.5	3.0	452.8	1.5	73.6
	116+58.50		116+88.50	30.0	3.0	10.0	1.5	1.6
N. RAMP	1000+19.00		1007+19.50	700.5	3.0	233.5	1.5	37.9
S. RAMP	1999+85.00		2009+04.00	919.0	3.0	306.3	1.5	49.8
							TOTAL =	2825.3
							USE =	2826.0

FILE NAME =	USER NAME = austinr1	DESIGNED -	REVISED -
ct:\pw\work\PWIDOT\AUSTINRL\dms86981\70256\deta11.s.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/23/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(143,R,144)RS-4		56	15
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70256	