

48101200 AGGREGATE SHOULDERS, TYPE B (CONT'D)

		STATION	TO	STATION	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ.YD)	SHOULDER THICKNESS (INCHES)	(TON)
<b>VETERANS PARKWAY RAMPS</b>									
RAMP E	RT	16+56.17		RT 36+99.51	2043.34	2	454.1	1.75	43.0
RAMP E	LT	22+04.00		LT 30+51.00	847	2	188.2	1.75	17.8
RAMP F	RT	9+92.00		RT 28+50.22	1858.22	2	412.9	1.75	39.1
RAMP F	LT	12+38.33		LT 23+81.00	1142.67	2	253.9	1.75	24.1
RAMP J	RT	0+00.00		RT 15+68.36	1568.36	2	348.5	1.75	33.0
RAMP J	RT	17+13.08		RT 22+68.96	555.88	2	123.5	1.75	11.7
RAMP J	LT	0+87.00		LT 13+47.00	1260	2	280.0	1.75	26.5
RAMP M	RT	30+00.00		RT 57+76.00	2776	2	616.9	1.75	58.5
RAMP M	LT	37+43.17		LT 48+62.00	1118.83	2	248.6	1.75	23.6
RAMP N	RT	0+00.00		RT 29+36.19	2936.19	2	652.5	1.75	61.9
RAMP N	LT	6+65.00		LT 19+00.00	1235	2	274.4	1.75	26.0
RAMP O	RT	0+00.00		RT 32+62.30	3262.3	2	725.0	1.75	68.7
RAMP O	LT	6+47.00		LT 23+26.00	1679	2	373.1	1.75	35.4

SUB-TOTAL = 469.4

**US 51 RAMPS**

RAMP A	RT	13+18.00		RT 24+83.97	1165.97	2	259.1	1.75	24.6
RAMP A	RT	26+61.56		RT 31+97.26	535.7	2	119.0	1.75	11.3
RAMP A	LT	15+50.00		LT 23+18.00	768	2	170.7	1.75	16.2
RAMP B	RT	44+40.00		RT 62+40.00	1800	2	400.0	1.75	37.9
RAMP B	LT	44+29.00		LT 55+00.00	1071	2	238.0	1.75	22.6
RAMP C	RT	5+36.00		RT 23+90.00	1854	2	412.0	1.75	39.1
RAMP C	LT	5+36.00		LT 13+93.00	857	2	190.4	1.75	18.1
RAMP D	RT	13+40.00		RT 23+86.72	1046.72	2	232.6	1.75	22.0
RAMP D	RT	25+64.30		RT 31+89.27	624.97	2	138.9	1.75	13.2
RAMP D	LT	13+40.00		LT 22+00.00	860	2	191.1	1.75	18.1
RAMP E	RT	3+58.87		RT 21+28.00	1769.13	2	393.1	1.75	37.3
RAMP E	LT	9+71.00		LT 21+28.00	1157	2	257.1	1.75	24.4
RAMP F	RT	13+77.00		RT 31+84.34	1807.34	2	401.6	1.75	38.1
RAMP F	LT	13+77.00		LT 22+61.00	884	2	196.4	1.75	18.6

SUB-TOTAL = 341.3

TOTAL = 2972.2

USE = 2972.0

**SHEET 15 OF 22**

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\SHERRERJM\dms83233\70605 SCHEDULES OF QUANT.dgn	DRAWN - JMS	REVISED -	74			57-20(1)&(57-4,5,6)RS-3	MCLEAN	160	34	
PLOT SCALE = 40.0000' / IN.	CHECKED - JMS	REVISED -	CONTRACT NO. 70505							
PLOT DATE = 1/30/2009	DATE - 01-22-2009	REVISED -	SCALE: _____			SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		