

SCHEDULE OF CLASS B PATCHING 13" (CONT'D)

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA			DOWEL BARS Z0017100 (Each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PAVEMENT FABRIC 44213100 (sq. yd)
					TYPE II 44201007 (sq. yd)	TYPE III 44201011 (sq. yd)	TYPE IV 44201013 (sq. yd)				
ROADWAY D											
720+74	WB	PL	6	12	8.0	0.0	0.0	20	48.0	0	0.0
720+50	WB	PL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
736+80	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
728+27	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
721+36	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
720+74	WB	DL	6	12	8.0	0.0	0.0	20	48.0	0	0.0
720+50	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
717+24	WB	PL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
717+24	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
703+59	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
696+99	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
696+35	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
694+24	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
690+00	WB	DL	10	12	13.3	0.0	0.0	20	56.0	0	0.0
687+50	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
687+28	WB	DL	70	12	0.0	0.0	93.3	20	176.0	35	93.3
685+00	WB	DL	10	12	13.3	0.0	0.0	20	56.0	0	0.0
684+19	WB	DL	12	12	0.0	16.0	0.0	20	60.0	0	16.0
681+94	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
680+79	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
675+91	WB	DL	50	12	0.0	0.0	66.7	20	136.0	25	66.7
677+99	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
677+65	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
648+01	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
643+20	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
643+80	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
649+40	WB	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
638+80	WB	DL	10	12	13.3	0.0	0.0	20	56.0	0	0.0
617+71	WB	DL	6	12	8.0	0.0	0.0	20	48.0	0	0.0
616+77	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
616+65	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
616+32	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
614+34	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
614+34	WB	PL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
611+24	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
610+13	WB	DL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
610+13	WB	PL	4	12	5.3	0.0	0.0	20	44.0	0	0.0
SUB-TOTAL =					232.0	16.0	160.0	660.0	1800.0	60.0	176.0
ROADWAY G											
604+50	NB	DL	75	12	0.0	0.0	100.0	20	186.0	38	100.0
605+50	B	DL	8	12	10.7	0.0	0.0	20	52.0	0	0.0
SUB-TOTAL =					445.3	32.0	420.0	1260.0	3614.0	158.0	452.0

(CONT'D NEXT SHEET)

SHEET 2 OF 6

FILE NAME =	USER NAME = shererjm	DESIGNED - JMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A. RTE. =	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PWIDOT\SHERRJ\ms83233\70505 SCHEDULES OF QUANT.dgn	DRAWN - JMS	REVISED -	74			57-20(1)&(57-4,5,6)RS-3	MCLEAN	160	43	
PLOT SCALE = 40.0000' / IN.	CHECKED - JMS	REVISED -	CONTRACT NO. 70505							
PLOT DATE = 1/30/2009	DATE - 01-22-2009	REVISED -	SCALE: _____			SHEET NO. ___ OF ___ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		