

F.I. R.T.E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(74,10-4,1)RS-1	*	69	6
S. A.		TO STA.		
FD. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* CHAMPAIGN & PIATT

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FAI - 74	
				100% FED	100% FED
				PIATT COUNTY	CHAMPAIGN COUNTY
				STA. 1258+09 TO	STA. 1324+09 TO
				STA. 1324+77.33	1501+00
				RURAL	RURAL
				100% FED	100% FED
				1000	1000
40800030	AGGREGATE (PRIME COAT)	TON	2.0	1.0	1.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	122.0	61.0	61.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,571.0	0.0	1,571.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	126,474.0	35,254.0	91,220.0
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	2,356.0	0.0	2,356.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,745.0	488.0	1,257.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	7,215.0	2,018.0	5,197.0
50105220	PIPE CULVERT REMOVAL	FOOT	20.0	10.0	10.0
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	20.0	10.0	10.0
63400105	GUARD POSTS	EACH	84.0	30.0	54.0
63400205	GUARD POSTS REMOVAL	EACH	84.0	30.0	54.0
64200105	SHOULDER RUMBLE STRIP	FOOT	96,622.0	27,029.0	69,593.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0	2.0	2.0
67100100	MOBILIZATION	L SUM	1.0	0.3	0.7
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2.0	0.0	2.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	0.3	0.7
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0	0.3	0.7
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5.0	2.0	3.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	26,088.0	7,298.0	18,790.0
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	96,623.0	27,030.0	69,593.0

(CONT'D NEXT PAGE)

SHEET 2 OF 3

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.I. ROUTE 74
 SECTION (74,10-4,1)RS-1
 CHAMPAIGN & PIATT COUNTY

SCALE: N/A
 DATE: 02-03-09

DRAWN BY: JMS
 CHECKED BY:

PLOT DATE = 2/6/2009
 FILE NAME = c:\pva\pva\pva\DOT\SHEREN\JMS\70527\sh1\road.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = sheren.jm