F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	43RS-3; 87-1RS-2	SCHUYLER	39	3
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT 72772

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

	ITEM	UNIT	TOTAL	1000 100% FEDERAL ESP
35800100	PREPARATION OF BASE	SQ YD	200	200
35800200	AGGREGATE BASE REPAIR	TON	50	50
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	63	63
40600300	AGGREGATE (PRIME COAT)	TON	236	236
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,590	4,590
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	331	331
40600990	TEMPORARY RAMP	SQ YD	88	88
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	20,346	20,346
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	13,564	13,564
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	352	352
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	161,115	161,115
44200144	PAVEMENT PATCHING, TYPE II, 12 INCH	SQ YD	456	456
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	SQ YD	156	156
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	413	413
48101200	AGGREGATE SHOULDERS, TYPE B	TON	6,897	6,897

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET 1 OF 3
FAP 3010 (US67)
SECTION 43RS-3;87-1RS-2
SCHUYLER COUNTY

SCALE: VERT. HORIZ.
DATE : JUNE, 2004

DRAWN BY DJK
CHECKED BY CAJ

c:\pw_work\PWIDOT\LAUGHLINRL\dms23072\SummaryQuantities.dgn
Feb-06-2009 02:19:50 PM laughlinrl