

100% FED

SUMMARY OF QUANTITIES				HDWL. REPAIR STA. 76+65		S.N. 009-2506		S.N. 009-2507	
				ROADWAY FAP 67	STRUCTURE S.N. 009-C100	ROADWAY FAP 67	STRUCTURE S.N. 009-2506	ROADWAY FAP 67	STRUCTURE S.N. 009-2507
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				1000-2A	X028-2A	1000-2A	X028-2A	1000-2A	X028-2A
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	36	36					
20100500	TREE REMOVAL, ACRES	ACRE	1.7			0.3		1.4	
20200100	EARTH EXCAVATION	CU. YD.	10660	228		3637		6795	
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU. YD.	50			25		25	
25000200	SEEDING, CLASS 2	ACRE	5.3	0.2		2.5		2.6	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	477	18		225		234	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	477	18		225		234	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	477	18		225		234	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	10.6	0.4		5.0		5.2	
25100115	MULCH, METHOD 2	ACRE	5.3	0.2		2.5		2.6	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1060	40		500		520	
28000400	PERIMETER EROSION BARRIER	FOOT	300			300			
28001000	AGGREGATE (EROSION CONTROL)	TON	175			70		105	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	3207	403		623		2181	
28200200	FILTER FABRIC	SQ. YD.	6405	806		1241		4358	
35501324	HOT-MIX ASPHALT BASE COURSE 10"	SQ. YD.	3603			1679		1924	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	288	12		145		131	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.7			1.9		1.8	
40600300	AGGREGATE PRIME COAT	TON	19.1			9.7		9.4	
40600635	LEVELING BINDER (MACHINE METHOD), N 70	TON	312			183		129	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	389			167		222	
40600990	TEMPORARY RAMP	SQ. YD.	73			25		48	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 70	TON	540			282		258	
44000100	PAVEMENT REMOVAL	SQ. YD.	514			184		330	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ. YD.	2078			999		1079	
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ. YD.	792			433		359	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	197			100		97	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	389			187		202	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1				1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1						1
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1				
50105220	PIPE CULVERT REMOVAL	FOOT	472	84		226		162	
50800105	REINFORCEMENT BARS	POUND	132050		16610		52200		63240
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2370		350				2020
50800515	BAR SPLICERS	EACH	242				133		109
51201600	FURNISHING STEEL PILES HP 12 X 53	FOOT	1104		600				504
51202305	DRIVING PILES	FOOT	1104		600				504
51203600	TEST PILE STEEL HP 12 X 53	EACH	4		2				2
51500100	NAME PLATES	EACH	2				1		1
54002020	EXPANSION BOLTS 3/4 INCH	EACH	56		56				
54003000	CONCRETE BOX CULVERTS	CU. YD.	806.3		114.1		327.6		364.6

FILE NAME = 0672875-sh1-500.dgn

USER NAME =
 PLOT SCALE =
 PLOT DATE = Feb-05-2009 05:03:19PM

DESIGNED - RKA
 DRAWN - RKA
 CHECKED - CPK
 DATE - 04/07/08



Allen Henderson & Associates, Inc.
 Civil and Structural Engineers Springfield, IL
 62709 Phone: (217)544-8033 IL Design Firm
 No. 184-001907

SUMMARY OF QUANTITIES
 SCALE: NONE SHEET NO. 3 OF 71 SHEETS STA. TO STA.

F.A.P. RTE. 67	SECTION (6X-1)B-2	COUNTY CASS	TOTAL SHEETS 71	SHEET NO. 3
CONTRACT NO. 72875				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				