

100% FED

SUMMARY OF QUANTITIES				HDWL. REPAIR STA. 76+65		S.N. 009-2506		S.N. 009-2507	
				ROADWAY FAP 67	STRUCTURE S.N. 009-2506	ROADWAY FAP 67	STRUCTURE S.N. 009-2506	ROADWAY FAP 67	STRUCTURE S.N. 009-2507
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE					
				1000-2A	X028-2A	1000-2A	X028-2A	1000-2A	X028-2A
54201483	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 18"	FOOT	326	90		44		192	
54201489	PIPE CULVERTS, TYPE 2, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 24"	FOOT	210			210			
54215553	METAL END SECTIONS 18"	EACH	8	2		2		4	
54215559	METAL END SECTIONS 24"	EACH	4			4			
60500050	REMOVING CATCH BASINS	EACH	1	1					
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	1660			660		1000	
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	25			15		10	
67000500	ENGINEERS FIELD OFFICE, TYPE B	CAL. MO.	8			4		4	
67100100	MOBILIZATION	L. SUM	1			0.5		0.5	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1			0.5		0.5	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L. SUM	1			0.5		0.5	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L. SUM	1			0.5		0.5	
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	2			1		1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DA	10			5		5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2			1		1	
70106800	CHANGEABLE MESSAGE SIGN	CAL. MO.	17	3		7		7	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	521			275		246	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	7119			3541		3578	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	3185			1591		1594	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1087.5			512.5		575	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	925			350		575	
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	6355			3082		3273	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	34			18		16	
78300100	PAVEMENT MARKING REMOVAL	SQ. FT.	1887			913		974	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	34			18		16	
X0321100	GEOTEXTILE RETAINING WALL	SQ. FT.	153.0				153.0		
X0323665	RIPRAP SLURRY	SQ. YD.	3409	806		1174		1429	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ. FT.	1736				853		883
X0324118	GRANULAR CULVERT BACKFILL	CU. YD.	3160				1600		1560
X7200201	WIDTH RESTRICTION SIGNING	L. SUM	1			0.5		0.5	
XX000610	RELOCATE EXISTING MAILBOX	EACH	1			1			
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1			0.5		0.5	
Z0015500	DEBRIS REMOVAL	L. SUM	1	.33		.33		.34	
Z0030260	IMPACT ATTENUATORS TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4			2		2	
Z0030330	IMPACT ATTENUATORS RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	4			2		2	
Z0054517	ROCKFILL - FOUNDATION	TON	811		66		375		370
Z0073100	TEMPORARY SHORING	EACH	1						1

• SPECIALTY ITEM

FILE NAME :  
0672875-sh1-500.dgn

USER NAME :

PLOT SCALE :

PLOT DATE : Feb-05-2009 08:51:47AM

DESIGNED - RKA  
DRAWN - RKA  
CHECKED - CPK  
DATE - 04/07/08

REVISED -  
REVISED -  
REVISED -  
REVISED -



Allen Henderson & Associates, Inc.  
Civil and Structural Engineers Springfield, IL  
62703 Phone: (217)544-8033 IL Design Firm  
No. 184-001907

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 71 SHEETS STA. TO STA.

F.A.P. RTE. 67	SECTION (6X-1)B-2	COUNTY CASS	TOTAL SHEETS 71	SHEET NO. 4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 72875				