

NOTE 1: RIPRAP SHALL EXTEND FAR ENOUGH UP THE SLOPES TO ALLOW 0.3m (1') OVERTOPPING TO AVOID ERODING AROUND THE EDGES OF THE RIPRAP.

NOTE 2: ENDS SHALL BE TIED INTO SLOPES.

## LEGEND FOR STORM WATER POLLUTION PREVENTION PLAN

ITEM	SYMBOL
AGGREGATE (EROSION CONTROL) [STONE DUMPED RIPRAP DITCH CHECKS: Height = 0.6m (2')]	<b>—</b>
TEMPORARY DITCH CHECKS	-\$-
INLET PIPE PROTECTION (I&PP)	$\Leftrightarrow$
EROSION CONTROL FENCE	
EARTH EXCAVATION FOR EROSION CONTROL (SEDIMENT BASINS)	
PRESERVE EXISTING TREES, WOODLANDS, AND UNDERSTORY (OUTSIDE CONSTRUCTION LIMITS)	
ITEM PLACED AT BEGINNING OF CONSTRUCTION (Requirement)	* [ITEM *
ITEM PLACED AS DIRECTED BY ENGINEER (When required by situation)	ITEM
DIRECTION OF OVERLAND FLOW	


## GENERAL NOTES:

All items shall be constructed as shown on this sheet, on Standard 280001, and as directed by the Engineer.

The symbology on the STORM WATER POLLUTION PREVENTION PLAN sheets does not represent the size or quantity of bales, for number of bales refer to details and notes shown on this sheet and/or as directed by the Engineer.

THE CONTRACTOR SHALL INSTALL DITCH CHECKS AS DIRECTED BY THE ENGINEER. IF THE ENGINEER ELECTS TO UTILIZE FLUSH RIPRAP DITCH CHECKS IN LIEU OF TEMPORARY DITCH CHECKS AS SHOWN ON THE FOLLOWING PLAN SHEETS, THE SPACING SHOULD BE DOUBLED.

FILE NAME =	USER NAME =	DESIGNED	-	RKA	REVISED	-	Γ
D672875-sht-swppp.dgn		DRAWN	-	RKA	REVISED	-	ı
	PLOT SCALE =	CHECKED	-	CPK	REVISED	-	l
	PLOT DATE = Jan-30-2009 09:38:41AM	DATE	-	04/07/08	REVISED	-	



I					F.A.P. SECTION			COUNTY	TOTAL SHEETS	SHEET NO.
l	STORM WATER POLLUTION PREVENTION PLAN			67	67 (6X-1)B-2		CASS	71	27	
							CONTRACT	L NO.	72875	
I	SCALE: NONE	SHEET NO. 27 OF 71 SHEETS	STA.	TO STA.	FED. F	ROAD DIST. NO.	ILLINOIS FED. A	ID PROJECT		