

SUMMARY OF QUANTITIES

100% FED

CONTRACT NO. 72923				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	.	MORGAN	137	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 128RS-3, 139RS-3				

ROADWAY  
FAU ROUTE 753  
STA 40+44.59 TO  
STA 151+50.21  
I000-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITY	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	37,250	37,250
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	645	645
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	179	179
44000600	SIDEWALK REMOVAL	SQ FT	3,025	3,025
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,794	1,794
44200132	PAVEMENT PATCHING, TYPE II, 11 INCH	SQ YD	728	728
44200136	PAVEMENT PATCHING, TYPE III, 11 INCH	SQ YD	238	238
44200138	PAVEMENT PATCHING, TYPE IV, 11 INCH	SQ YD	413	413
48101200	AGGREGATE SHOULDERS, TYPE B	TON	975	975
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,630	2,630
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,014	1,014
48301000	PROTECTIVE COAT	SQ YD	2,014	2,014
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1
50105220	PIPE CULVERT REMOVAL	FOOT	908	908
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	78	78
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	215	215
55100900	STORM SEWER REMOVAL 18"	FOOT	24	24
56106300	ADJUSTING WATER MAIN 6"	FOOT	40	40
56109300	WATER VALVES TO BE MOVED	EACH	1	1
56500300	DOMESTIC METER VAULTS TO BE ADJUSTED	EACH	4	4
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	2
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	1,606	1,606

• SPECIALTY ITEM

PLT DATE = Jan-18-2008 09:46:00AM  
 PLT USER = JLD  
 USER NAME = jld

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL RTE 104  
SUMMARY OF QUANTITIES

DATE NOVEMBER 2, 2007  
 DRAWN BY TJD  
 CHECKED BY AWM