CONTRACT NO. 72923

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	•	MORGAN	137	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• 128RS-3, 139RS-3

STORM SEWER AND PIPE CULVERT SCHEDULE

STRUCTURE	STATION	OFFSET	SIDE	TYPE	STANDARD AND DESIGN NUMBER	STORM SEWER WATERMAIN REQUIREMENTS 12"	18"	24"	30"	36"	CL. A TY. 2 36"	MANHOLES 4' A-8	5' A-1	A-1-C	A-8	A-9	6' A-1-C	A-8	A-9	6' SPECIAL A-1-C	7' A-1-C	8' A-3V	8' SPECIAL A-3	A-3V	TYPE A A-3V	A-8	A-9	TYPE B B-8	B-9	PRC FLARED END SECTION 18"	36"	PIPE CULVERT CS/A TYPE 1 15"	TRENCH BACKFILL	CONTROLLED LOW-STRENGTH MATERIAL
						FOOT						EACH																					FOOT	CU YD	
FAU ROUTE 753 (IL RTE 104)																																			
SS	110+12.00	27.0	LT	MH	602406, 602601, 602701, 604001												1																		
				SS						64.1																									84
V	110+77.00	22.9	LT	MH	602411, 602601, 602701, 604001																1														
				SS						25.3																									37
X	110+78.02	51.8	LT	MH	602401, 602601, 602701, 604036							1																							
				SS			26.6																												20
Y	111+05.00	21.0	LT	MH	602401, 602601, 602701, 604041											1																			
				SS						106.9																									176
II	111+67.87	25.9	RT	INLET	602301, 604036																					1									
AA	112+14.00	22.0	LT	MH	602401, 602601, 602701, 604001								1																						
				SS						68.5																									109
TT	112+84.00	22.0	LT	INLET	602301, 604036																					1									
				SS		6.2																													3
BB	112+84.00	15.0	LT	MH	602401, 602601, 602701, 604001									1																					
				SS						67.5																									112
DD	113+53.00	23.0	LT	INLET	602301, 604036																					1									
				SS		7.0																													3
CC	113+53.00	15.0	LT	MH	602401, 604601, 602701, 604001									1																					
				SS						48.3																									81
FF	114+03.00	25.0	LT	INLET	602301, 604036																					1									
				SS		9.0																												2	2
EE	114+03.00	15.0	LT	MH	602401, 602601, 602701, 604001									1																					
				SS						114.7																								34	150
GG	115+20.00	23.0	LT	MH	602401, 602601, 602701, 604036										1																				
				SS						163.4																								217	
HH	116+85.00	25.5	LT	MH	602401, 602601, 602701, 604036										1																				
				SS						183.5																								232	
	117+36.05	24.6	RT	CULVERT																													38.0		
KK	118+66.50	26.0	LT	MH	602406, 602601, 602701, 604036													1																	
				SS						63.3																								38	56
	121+29.00	24.2	RT	CULVERT																													40.0		
ROUTE 111																																			
RR	7+56.02	31.9	LT	END SEC	542301																									1					
				SS			121.3																											29	
QQ	8+80.00	33.8	LT	MH	602401, 602601, 602701, 604036							1																							
				SS			66.5																											23	
MORGAN STREET																																			
PP	7+06.39	20.3	LT	END SEC	542301																										1				
				SS						12.9																								14	
OO	7+15.00	7.0	LT	MH	602406, 602601, 602701, 604001												1																		
				SS							73.4																							69	
NN	7+90.00	15.0	LT	MH	602401, 602601, 602701, 604036										1																				
				SS							113.3																							118	
MM	9+06.00	15.0	LT	MH	602401, 602601, 602701, 604036										1																				
				SS							28.0																							43	
LL	9+36.00	15.0	LT	MH	602406, 602601, 602701, 604001												1																		
TOTAL						343.0	354.3	486.5	206.4	935.7	214.7	2	1	3	6	8	3	1	1	1	1	1	1	1	1	5	5	2	3	1	1	78.0	859.0	1606.0
USE						343	355	487	207	936	215	2	1	3	6	8	3	1	1	1	1	1	1	1	1	5	5	2	3	1	1	78	859	1,606

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

IL ROUTE 104
SCHEDULES OF QUANTITIES

SCALE: VERT. HORIZ.
DATE NOVEMBER 2, 2007

DRAWN BY TJD
CHECKED BY AWM

PLOT DATE = Jan-16-2009 8:47:14AM
FILE NAME = S:\CADD\72923 D9854784\D9854784\CADData\CADsheets\2447-18ca002.dgn
PLOT SCALE = 2.1176 / IN.
USER NAME = IaugHurs