

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEMS	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE TYPE			
				100% FED.		SFTY-1B RURAL	
				1000- RURAL	1000- RURAL	SFTY-1B RURAL	SFTY-1B RURAL
				F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)	F.A.P. 781 (IL. RTE. 33)
				0+915.000 TO 2+756.900 AND 4+475.071 TO 4+874.474	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071	2+756.900 TO 4+475.071
• MX032196	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ M	8.0	8.0			
Δ MX032200	ENGINEERED BARRIER	SQ M	457		457		
• MX032509	GRADING AND SHAPING SPECIAL	SQ M	9,815		9,815		
MX033694	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 125 MM)	SQ M	0.4	0.4			
MX033731	PRECAST CONCRETE BOX CULVERT 900MM x 450MM	METER	5.2	5.2			
MX033734	PRECAST CONCRETE BOX CULVERT 1.8M x 0.6M (M273)	METER	15.3	15.3			
MX540110	PRECAST CONCRETE BOX CULVERT 1.5M x 0.6M	METER	64.4		64.4		
• MZ034730	MODULAR RETAINING WALL SYSTEM	SQ M	97.1		97.1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6			
Z0030350	IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6	6			
⊙ Z0076600	TRAINEES	HOUR	500	400	100		
28000300	TEMPORARY DITCH CHECKS	EACH	91	90	1		
28000500	INLET AND PIPE PROTECTION	EACH	17	16	1		
• 50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1		
• 50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1		
• 50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1		
• 50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1		1		
• 50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1		1		
• 50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1		1		
• 50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1		1		
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	2	2			

- \* SEE SPECIAL PROVISIONS
- Δ Specialty Items
- ⊙ Y08D

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE		DRAWN BY KOJ
DATE FEBRUARY 6, 2009		CHECKED BY LWJ

PLOT DATE = 2/17/2009  
 FILE NAME = H:\4428\Contract 74349\SHI\_084\_summ\_V8.dgn