

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	22
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**EARTHWORK SCHEDULE**

LOCATION		RT/LT	EARTH EXCAVATION	EARTH EXCAVATION (WIDENING)	EMBANKMENT REQUIRED	EMBANKMENT REQUIRED FOR ENTRANCES (SEE NOTE)	EARTH EXCAVATION AVAILABLE (ADJUSTED FOR SHRINKAGE - 25%)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	TOPSOIL EXCAVATION AND PLACEMENT
			M2020010	M2020050			CU. M.		
STATION			CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.	CU. M.
<b>RLR/L</b>									
STA. 0+915 TO STA. 2+756.900		RT/LT	10,207.7	497.3	4,069.7	1,120.3	8,028.8	2,838.8	3,634.0
STA. 1+970 (TR 1000)		RT.	173.3		44.0		130.0	86.0	23.8
			10,381.0	497.3	4,113.7	1,120.3	8,158.8	2,924.8	3,657.8
<b>BLONG</b>									
STA. 2+756.900 TO STA. 4+475		RT/LT	1,253.7		1,416.6		940.3	-476.4	9.7
STA. 2+767.5 (TR 150)		LT.	74.9		28.2		56.2	28.0	
STA. 2+892.1 (JOY STREET)		LT.	45.2		8.9		33.9	25.0	
STA. 2+977.3 (MADISON STREET)		LT.	72.9		4.6		54.7	50.1	
STA. 3+122.6 (JEFFERSON STREET)		LT.	63.0		2.9		47.3	44.4	
STA. 3+122.6 (JEFFERSON STREET)		RT.	94.6		4.1		71.0	66.9	
STA. 3+211.3 (WASHINGTON STREET)		LT.	16.5		5.1		12.4	7.3	
STA. 3+211.3 (WASHINGTON STREET)		RT.	46.0		2.8		34.5	31.7	
STA. 3+298.2 (JACKSON STREET)		LT.	45.7		4.3		34.3	30.0	
STA. 3+298.2 (JACKSON STREET)		RT.	80.8		6.3		60.6	54.3	
STA. 3+385.0 (WILSON STREET)		LT.	18.6		7.1		14.0	6.9	
STA. 3+472.4 (ADAMS STREET)		RT.	3.1		9.4		2.3	-7.1	
STA. 3+572.1 (RANGE STREET)		RT.	23.8		1.8		17.9	16.1	
STA. 3+572.7 (RANGE STREET)		LT.	37.3		1.3		28.0	26.7	
STA. 3+659.2 (GARFIELD STREET)		LT.	34.4		0.2		25.8	25.6	
STA. 3+659.2 (GARFIELD STREET)		RT.	26.2		2.6		19.7	17.1	
STA. 3+745.8 (GRANT STREET)		LT.	20.3		6.5		15.2	8.7	
STA. 3+746 (GRANT STREET)		RT.	47.2		5.6		35.4	29.8	
STA. 3+832.3 (HARRISON STREET)		LT.	118.1		4.2		88.6	84.4	
STA. 3+919 (TAYLOR STREET)		LT.	15.8		28.0		11.9	-16.2	
STA. 3+919 (TAYLOR STREET)		RT.	16.6		38.5		12.5	-26.1	
STA. 4+155.8 (ROOSEVELT STREET)		RT.	33.0		3.2		24.8	21.6	
			2,187.7	0.0	1,592.2	0.0	1,640.8	48.5	9.7
<b>RLR/L</b>									
STA. 4+475 TO STA. 4+874.474		RT/LT	623.3	48.6	142.6	2,066.7	503.9	-1,705.4	300.6
TOTALS			13,192.0	545.9	5,848.4	3,187.0	10,303.4	1,268.0	3,968.1
TOTALS ROUNDED FOR SUMMARY SHEET			13,195	550					3,970

NOTE: QUANTITIES ASSUME ALL EXISTING ENTRANCES (NOT INCLUDING PUBLIC ROADS) WILL BE REMOVED DURING DITCH EXCAVATION.

PLOT DATE = 2/6/2009  
FILE NAME = H:\4420\Contract 74349\BHT\_014\_sch\_all\_schedules\_V8.dgn

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULE OF QUANTITIES
SCALE	NO SCALE	DRAWN BY KOJ
DATE	FEBRUARY 6, 2009	CHECKED BY LWJ