

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	25
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

TEMPORARY DITCH CHECKS

STATION	SIDE	EACH	STATION	SIDE	EACH
RURAL					
0+930	RT	1	2+045	LT	1
0+975	LT&RT	2	2+055	RT	1
1+020	LT&RT	2	2+100	RT	1
1+050	LT&RT	2	2+140	LT&RT	2
1+060	LT&RT	2	2+145	LT&RT	2
1+100	LT&RT	2	2+190	RT	1
1+195	RT	1	2+235	LT&RT	2
1+235	LT&RT	2	2+280	LT&RT	2
1+240	LT&RT	2	2+325	LT&RT	2
1+285	LT&RT	2	2+370	LT&RT	2
1+330	LT&RT	2	2+415	LT	1
1+425	LT	1	2+460	LT&RT	2
1+470	LT&RT	2	2+505	LT&RT	2
1+515	LT&RT	2	2+550	RT	1
1+525	LT&RT	2	2+595	RT	1
1+570	LT&RT	2	2+640	LT&RT	2
1+615	LT	1	2+685	LT&RT	2
1+660	LT&RT	2	2+726	LT&RT	2
1+795	LT&RT	2	2+731	LT&RT	2
1+825	LT&RT	2	SUBTOTAL		31
1+840	LT&RT	2	OBLONG		
1+855	LT&RT	2	4+405	RT	1
1+870	LT&RT	2	RURAL		
1+880	LT&RT	2	4+495	LT&RT	2
1+885	LT&RT	2	4+520	LT	1
1+900	RT	1	4+540	LT	1
1+907	LT	1	4+565	RT	1
1+915	RT	1	4+655	LT&RT	2
1+930	LT&RT	2	SUBTOTAL		7
2+000	LT	1	TOTAL		
SUBTOTAL		52	91		

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

LOCATION			EACH
STATION	METERS	LT/RT	
RURAL			
0+882.214	12.192	LT	1
0+902.439	12.192	RT	1
1+327.571	12.192	RT	1
1+358.051	15.240	RT	1
1+449.491	12.192	LT	1
1+479.971	15.240	RT	1
1+510.451	18.288	LT	1
1+510.451	18.288	RT	1
1+540.932	18.288	LT	1
1+540.932	18.288	RT	1
1+571.412	12.192	LT	1
1+574.460	12.192	RT	1
1+708.572	12.192	LT	1
1+723.812	12.192	RT	1
1+739.052	16.764	LT	1
1+754.292	16.764	RT	1
1+815.252	16.764	RT	1
1+845.732	16.764	LT	1
1+860.972	19.812	RT	1
1+887.948	18.288	LT	1
1+906.692	19.812	RT	1
1+946.357	14.935	RT	1
2+014.080	24.384	RT	1
2+113.592	18.288	LT	1
2+113.592	24.384	RT	1
2+206.770	18.288	LT	1
2+237.250	16.764	LT	1
2+328.690	24.384	RT	1
2+359.170	21.336	RT	1
2+481.073	16.764	LT	1
2+663.953	16.764	LT	1
2+675.230	16.764	LT	1
SUBTOTAL			32
OBLONG			
2+756.935	16.764	LT	1
2+761.396	22.860	LT	1
SUBTOTAL			2
TOTAL			34

PERMANENT SURVEY MARKERS, TYPE 1

DESCRIPTION	STATION	EACH
RURAL		
PC	1+887.948	1
PI	2+006.106	1
PT	2+113.592	1
		3
OBLONG		
PI	4+168.229	1
PC	4+374.882	1
PI	4+401.662	1
PT	4+428.404	1
		4
RURAL		
PC	4+679.693	1
PI	4+767.620	1
PT	4+854.953	1
		3
TOTAL		10

EROSION CONTROL

LOCATION				EROSION CONTROL BLANKET	STONE DUMPED RIPRAP, CLASS A4	FILTER FABRIC	AGGREGATE DITCH
STATION	TO	STATION	LT/RT	M2510630 SQ. METER	M2810707 SQ. METER	M2820200 SQ. METER	M2830400 M. TON
RURAL							
1+052.7	TO	1+055.9	LT		14.7	14.7	
1+052.7	TO	1+055.9	RT		11.7	11.7	
1+517.7	TO	1+522.3	LT		18.0	18.0	
1+517.7	TO	1+535.0	RT		92.2	92.2	
1+825.0	TO	1+884.8	LT	110.0	168.8	168.8	
1+825.0	TO	1+925.0	RT	190.0	262.3	262.3	
2+053.6	TO	2+142.6	RT	498.2			
2+142.6	TO	2+146.0	LT		16.9	16.9	
2+142.6	TO	2+146.0	RT		33.9	33.9	
2+146.0	TO	2+393.0	RT	1,333.7			
2+413.6	TO	2+698.0	RT	1,535.0			
2+698.0	TO	2+702.0	LT		14.4	14.4	
2+698.0	TO	2+756.0	RT		318.3	318.3	
				3,666.9	951.2	951.2	0.0
OBLONG							
2+755.0	TO	2+759.5	LT		14.7	14.7	
2+762.0	TO	2+773.8	RT		115.5	115.5	
3+960.0	TO	3+963.0	LT		15.3	15.3	
				0.0	145.5	145.5	0.0
RURAL							
4+473.6	TO	4+478.8	LT		27.5	27.5	
4+473.6	TO	4+478.8	RT		31.2	31.2	
4+478.8	TO	4+574.1	LT			223.5	119.6
4+592.8	TO	4+610.4	LT			42.8	22.9
4+478.8	TO	4+520.0	RT			100.4	53.7
4+538.0	TO	4+590.2	RT			127.1	68.0
4+612.5	TO	4+634.2	RT			52.9	28.3
				0.0	58.7	605.4	292.5
TOTAL				3,666.9	1,155.4	1,702.1	292.5
TOTALS ROUNDED FOR SUMMARY SHEET				3,667	1,156	1,703	293

PLT DATE = 2/6/2009
FILE NAME = H:\4420\Contract 74349\SH1.014_sch.dwg

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE NO SCALE DRAWN BY KOJ</p> <p>DATE CHECKED BY</p>