

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	29
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PIPE CULVERT SCHEDULE

LOCATION		TYPE	TRENCH BACKFILL	PIPE CULVERTS					PRECAST REINFORCED CONCRETE FLARED END SECTIONS		END SECTIONS			
				RCCP		CLASS D								
				TYPE 1 450	TYPE 1 1500	TYPE 1 375	TYPE 1 450	TYPE 1 600						
STATION	RT/LT/AR		CUBIC METER	METER	METER	METER	METER	METER	EACH	EACH	EACH	EACH	EACH	
RURAL														
STA 0+952.000	RT	PIPE CULVERTS					10.36						2	
STA 1+201.500	LT	PIPE CULVERTS					8.84						2	
STA 1+392.000	LT	PIPE CULVERTS	6.91	18.29					2					
STA 1+465.000	LT	PIPE CULVERTS						10.36						
STA 1+465.000	RT	PIPE CULVERTS						12.50						
STA 1+595.600	RT	PIPE CULVERTS					10.97						2	
STA 1+755.200	LT	PIPE CULVERTS					10.67						2	
STA 1+764.500	RT	PIPE CULVERTS					15.85						2	
STA 2+196.000	LT	PIPE CULVERTS						11.58						2
STA 2+403.300	RT	PIPE CULVERTS	20.15		17.37					2				
STA 2+534.000	LT	PIPE CULVERTS				13.41					2			
OBLONG SEE STORM SEWER SCHEDULE														
RURAL														
STA 4+529.000	RT	PIPE CULVERTS					16.76						4	
STA 4+583.500	LT	PIPE CULVERTS					17.07						2	
STA 4+601.300	RT	PIPE CULVERTS					42.68						4	
STA 4+618.800	LT	PIPE CULVERTS					15.54						2	
TOTALS			27.06	18.29	17.37	13.4	148.74	34.44	2	2	2	22	2	
TOTALS ROUNDED FOR SUMMARY SHEET			28	18.5	17.5	13.5	149.0	34.5	2	2	2	22	2	

PLOT DATE = 2/6/2009
 FILE NAME = H:\4420\Contract\74349\SHI_027_sch_pipeculverts_v8.dgn

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		PIPE CULVERT SCHEDULE SCALE _____ DRAWN BY KOJ DATE FEBRUARY 6, 2009 CHECKED BY LWJ