

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
781	2ZRS-1	CRAWFORD	191	32
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE (CONTINUED)

STR #	UPSTREAM STRUCTURE			DOWNSTREAM STRUCTURE			TRENCH BACKFILL M2080150 CU M	STORM SEWERS, CLASS B TYPE 1 150MM METER	STORM SEWERS, CLASS A								RESTRICTED DEPTH MANHOLES						INLETS, TYPE A			INLETS, TYPE B	
	LOCATION			LOCATION					TYPE 1								TYPE 1 FRAME, CLOSED LID			TYPE 3 FRAME AND GRATE			TYPE 3 FRAME AND GRATE	TYPE 8 FRAME AND GRATE	TYPE 11 FRAME AND GRATE	TYPE 3 FRAME AND GRATE	TYPE 8 FRAME AND GRATE
	STATION	OFFSET METER	LT/RT	STATION	OFFSET METER	LT/RT			300MM	450MM	600MM	750MM	900MM	1050MM	1.2 M	1.5 M	1.8 M	2.4 M	1.2 M	1.5 M	1.8 M	60235700	60236200	60236800	60240220	60240301	
137	3+291.348	6.200	RT	138	3+291.348	6.200	LT	10.330																	1		
139	3+263.000	4.475	RT	140	3+263.000	4.475	LT	5.738													1						
140	3+263.000	-4.475	LT	0	3+263.000	6.200	LT			8.496											1						
186	3+216.576	14.300	RT	141	3+218.395	6.000	RT	4.262		7.860																1	
141	3+218.395	6.000	RT	142	3+230.000	4.475	RT	5.161		10.886																1	
142	3+230.000	4.475	RT	143	3+230.000	4.475	LT	6.678																			1
143	3+230.000	-4.475	LT	144	3+230.000	6.200	LT	0.218																			1
145	3+215.745	-10.600	LT	0	3+215.745	6.200	LT			4.173											1						
0	3+206.645	14.300	RT	147	3+204.448	6.200	RT			7.200																	
148	3+192.000	4.475	RT	0	3+192.000	6.200	RT			1.498																	1
149	3+173.000	4.475	RT	150	3+173.000	6.200	RT	0.280		0.606																	1
151	3+152.000	-4.475	LT	152	3+152.000	4.475	RT	6.457		8.496																	1
152	3+152.000	4.475	RT	0	3+152.000	6.200	RT			1.498																	1
155	3+129.452	-6.200	LT	156	3+115.748	6.200	LT	6.570		13.067																	1
156	3+115.748	-6.200	LT	158	3+115.748	6.200	RT	5.973		11.099																	1
157	3+118.225	12.200	RT	158	3+115.748	6.200	RT	3.240		5.372																	1
159	3+090.000	4.475	RT	0	3+090.000	6.200	RT			1.498																	1
160	3+062.000	-4.475	LT	161	3+062.000	4.475	RT	4.087		8.496																	1
161	3+062.000	4.475	RT	162	3+062.000	6.200	RT	0.274		0.606																	1
163	3+036.000	4.475	RT	0	3+036.000	6.200	RT			1.498																	1
164	3+010.000	-4.475	LT	165	3+010.000	4.475	RT	5.997		8.496																	1
165	3+010.000	4.475	RT	0	3+010.000	6.200	RT			1.498																	1
166	2+984.395	-6.000	LT	167	2+970.205	6.000	LT	6.367		13.553																	1
167	2+970.205	-6.000	LT	168	2+970.205	4.475	RT	4.656		9.656																	1
168	2+970.205	4.475	RT	169	2+970.205	6.200	RT	0.133		0.424																	1
170	2+927.500	-4.475	LT	171	2+927.500	4.475	RT	6.311		8.496																	1
171	2+927.500	4.475	RT	0	2+927.500	6.200	RT			1.498																	1
172	2+905.000	-6.200	LT	174	2+885.248	6.200	LT	13.604		19.115																	1
174	2+885.248	-6.200	LT	175	2+885.248	4.475	RT	7.428		9.856																	1
175	2+885.248	4.475	RT	0	2+885.248	6.200	RT			1.315																	1
176	2+863.000	-6.500	LT	177	2+863.000	4.475	LT	0.877		1.571																	1
177	2+863.000	-4.475	LT	179	2+863.000	6.200	RT	7.116																			1
178	2+863.000	8.300	RT	179	2+863.000	6.200	RT	0.580																			1
180	2+833.000	4.475	RT	0	2+833.000	6.200	RT			1.498																	1
181	2+803.000	4.475	RT	183	2+803.000	6.200	RT	16.205																			1
182	2+803.000	8.300	RT	183	2+803.000	6.200	RT	24.871																			1
173	2+896.595	-10.300	LT	0	2+896.595	6.200	LT			3.873																	1
300	3+576.965	11.800	RT	301	3+576.974	10.300	RT	0.380		0.863																	1
301	3+576.974	10.300	RT	302	3+582.000	6.375	RT	3.145		5.558																	1
302	3+582.000	6.375	RT	304	3+582.000	4.500	LT	8.496																			1
304	3+582.000	4.500	LT	307	3+617.600	4.500	LT	41.553																			1
307	3+617.600	4.500	LT	313	3+657.000	4.500	LT	45.148																			1
313	3+657.000	4.500	LT	319	3+690.350	4.500	LT	36.851																			1
319	3+690.350	4.500	LT	322	3+723.000	4.500	LT	36.343																			1
322	3+723.000	4.500	LT	326	3+739.000	4.500	LT	17.223																			1
326	3+739.000	4.500	LT	327	3+752.652	6.200	LT	14.565																			1
327	3+752.652	6.200	LT	333	3+800.000	6.200	LT	61.352																			1
333	3+800.000	6.200	LT	338	3+845.000	6.200	LT	58.171																			1
338	3+845.000	6.200	LT	341	3+876.000	6.200	LT	34.313																			1
341	3+876.000	6.200	LT	342	3+899.656	6.200	LT	26.749																			1
342	3+901.180	6.200	LT	401	3+960.405	6.200	LT			59.225																	1
401	3+960.405	6.200	LT	402	3+961.400	7.195	LT			1.407																	1
402	3+961.400	7.195	LT	403	3+961.400	11.000	LT			3.805																	1
303	3+582.000	6.375	LT	304	3+582.000	4.500	LT	0.444		1.073																	1
305	3+617.600	6.375	RT	307	3+617.600	4.500	LT	5.633		10.073																	1
306	3+617.600	6.375	LT	307	3+617.600	4.500	LT	0.430		1.073																	1
308	3+654.825	12.000	RT	309	3+656.750	12.000	RT	0.602		1.123																	1
309	3+656.750	12.000	RT	312	3+657.000	6.850	RT	2.285		3.847																	1
312	3+657.000	6.850	RT	313	3+657.000	4.500	LT	8.287																			1
314	3+654.825	11.900	LT	315	3+657.130	11.900	LT	0.574		1.503																	1

CONTINUED

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>STORM SEWER SCHEDULE</p> <p>SCALE _____ DRAWN BY KOJ</p> <p>DATE FEBRUARY 6, 2009 CHECKED BY LWJ</p>

FOR MORE ITEMS, SEE NEXT SHEET