ROUTE: US 41(Washington St. to S/O IL 132)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Washington	IL 132	NB	1&2	2	1500	2250	250	250						
		NB	1&2	3	500	1500	167	167						
		NB	1	12	30	360	40					40		
		NB	2	12	30	360	40					40		
		NB	1	6	12	72	8			8				
		NB	2	6	12	72	8			8				
		NB	1	4	4	16	2		2					
		NB	2	4	4	16	2		2					
		NB	1	6	12	72	8			8				
		NB	2	4	12	48	5			5				
		NB	1	4	12	48	5			5				
		NB	1	4	12	48	5			5				
		NB	1	4	12	48	5			5				
		NB	1	8	12	96	11			11				
		NB	1	8	12	96	11			11				
		NB	2	8	12	96	11			11				
		NB	2	8	12	96	11			11				
		NB	1	4	12	48	5			5				
		NB	2	6	12	72	8			8				
		NB	2	4	30	120	13			13				
		NB	2	4	6	24	3		3					
		NB	2	4	6	24	3		3					
		NB	2	4	12	48	5			5				
		NB	1	4	12	48	5			5				
		NB	2	4	12	48	5			5				
		NB	1	4	12	48	5			5				
		NB	2	12	12	144	16				16			
		NB	2	4	12	48	5			5				
		NB	2	4	4	16	2		2					
		NB	2	4	4	16	2		2					
		NB	2	4	100	400	44	44						
		NB	2	6	150	900	100	100						
		NB	2	6	100	600	67	67						
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	1&2	2	1500	2250	250	250						
		SB	1&2	3	500	1500	167	500						
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	1	4	12	48	5			5				
		SB	1	4	6	24	3		3					
		SB	2	4	4	16	2		2					
		SB	2	4	12	48	5			5				
		SB	2	4	6	24	3		3					
		SB	2	4	4	16	2		2					
		SB	2	6	30	180	20				20			
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	12	48	5			5				
		SB	Ramp	12	30	360	40					40		
		SB	1	4	4	16	2		2					
		SB	1	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	2	4	4	16	2		2					
		SB	1	4	8	32	4		4					
		SB	1	4	8	32	4		4					
		SB	2	4	8	32	4		4					
		SB	2	4	8	32	4		4					
		SB	1	4	12	48	5			5				
		SB	1	4	12	48	5			5				
		SB	2	4	12	48	5			5				
		SB	2	4	12	48	5			5				
		TOTALS						1378 SY	53 SY	177 SY	36 SY	120 SY	2000 FT	40 EACH

FILE NAME = c:\projects\d136308\design.se.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 41

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	21
		CONTRACT NO. 60E35		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT