ROUTE: IL Rte 22 (Rte 43 to Westminster Way)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
600' east of Rte 43	Rte 43	WB	2	1	1	1	1		1					
600' east of Rte 43	Rte 43	WB	1	2	2	4	1		1					
600' east of Rte 43	Rte 43	WB	2	2	2	4	1		1					
600' east of Rte 43	Rte 43	WB	2	2	2	4	1		1					
Rte 43	Lakeside Dr	WB	1	2	2	4	1		1					
Rte 43	Lakeside Dr	WB	1	2	12	24	3		3					
Rte 43	Lakeside Dr	WB	1	3	900	2700	300	300						
Rte 43	Lakeside Dr	WB	1	4	4	16	2		2					
Rte 43	Lakeside Dr	WB	1	3	6	18	2		2					
Rte 43	Lakeside Dr	WB	1	1	1	1	1		1					
Rte 43	Lakeside Dr	WB	1	2	2	4	1		1					
Rte 43	Lakeside Dr	WB	1	1	1	1	1		1					
Rte 43	Lakeside Dr	WB	1	2	4	8	1		1					
Rte 43	Lakeside Dr	WB	1	1	1	1	1		1					
Rte 43	Lakeside Dr	WB	1	2	2	4	1		1					
Rte 43	Lakeside Dr	WB	1	6	6	36	4		4					
Rte 43	Lakeside Dr	WB	1	2	4	8	1		1					
Rte 43	Lakeside Dr	WB	1	6	6	36	4		4					
Rte 43	Lakeside Dr	WB	1	1	1	1	1		1					
Rte 43	Lakeside Dr	WB	1	1	1	1	1		1					
Rte 43	Lakeside Dr	WB	2	2	4	8	1		1					
Rte 43	Lakeside Dr	WB	2	2	4	8	1		1					
Rte 43	Lakeside Dr	WB	2	3	300	900	100	100						
Lakeside Dr	I94 Tollway	WB	2	2	2	4	1		1					
Lakeside Dr	I94 Tollway	WB	2	2	1	2	1		1					
Lakeside Dr	I94 Tollway	WB	2	2	1	2	1		1					
Lakeside Dr	I94 Tollway	WB	2	3	400	1200	133	133						
I94 Tollway	200' west of Hewitt Dr	WB	1	3	1	3	1		1					
I94 Tollway	200' west of Hewitt Dr	WB	2	1	1	1	1		1					
I94 Tollway	200' west of Hewitt Dr	WB	LT TL	3	100	300	33	33						
I94 Tollway	200' west of Hewitt Dr	WB	1	12	2	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	2	12	2	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	1	3	8	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	2	3	7	21	2		2					
I94 Tollway	200' west of Hewitt Dr	WB	1	3	6	18	2		2					
I94 Tollway	200' west of Hewitt Dr	WB	1	2	2	4	1		1					
I94 Tollway	200' west of Hewitt Dr	WB	1	3	6	18	2		2					
I94 Tollway	200' west of Hewitt Dr	WB	1	2	2	4	1		1					
I94 Tollway	200' west of Hewitt Dr	WB	2	2	2	4	1		1					
I94 Tollway	200' west of Hewitt Dr	WB	2	3	12	36	4		4					
I94 Tollway	200' west of Hewitt Dr	WB	2	3	8	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	1	4	6	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	1	12	2	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	2	1	8	8	1		1					
I94 Tollway	200' west of Hewitt Dr	WB	1	4	6	24	3		3					
I94 Tollway	200' west of Hewitt Dr	WB	2	12	4	48	5			5				
I94 Tollway	200' west of Hewitt Dr	WB	2	1	1	1	1		1					
TOTALS:								775 SY	141 SY	36 SY	48 SY		1160 FT	24 EACH

FILE NAME = c:\projects\d136308\design_aa.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 22

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	34

CONTRACT NO. 60E35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT