ROUTE: IL Rte 43 (Talbot Ave to Albrecht Dr)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Talbot Ave	Foster Ave	SB	2	3	1600	4800	533	533						
Talbot Ave	Foster Ave	SB	1	12	6	72	8			8				
Talbot Ave	Foster Ave	SB	2	12	6	72	8			8				
Talbot Ave	Foster Ave	SB	2	2	2	4	1		1					
Talbot Ave	Foster Ave	SB	2	2	2	4	1		1					
Talbot Ave	Foster Ave	SB	1	12	250	3000	333	333						
Talbot Ave	Foster Ave	SB	1	12	150	1800	200	200						
Talbot Ave	Foster Ave	SB	1	12	30	360	40					40		
Talbot Ave	Foster Ave	SB	1	12	25	300	33					33		
Foster Ave	IL Rte 176	SB	2	3	1500	4500	500	500						
Foster Ave	IL Rte 176	SB	2	12	6	72	8			8				
Foster Ave	IL Rte 176	SB	1	12	6	72	8			8				
Foster Ave	IL Rte 176	SB	2	12	6	72	8			8				
Foster Ave	IL Rte 176	SB	1	12	6	72	8			8				
Foster Ave	IL Rte 176	SB	2	12	6	72	8			8				
Foster Ave	IL Rte 176	SB	2	3	25	75	8			8				
IL Rte 176	Albrecht Dr	SB	2	3	1500	4500	500	500						
IL Rte 176	Albrecht Dr	SB	2	2	2	4	1		1					
IL Rte 176	Albrecht Dr	SB	2	2	24	48	5			5				
IL Rte 176	Albrecht Dr	SB	1	12	150	1800	200	200						
IL Rte 176	Albrecht Dr	SB	2	12	5	60	7			7				
IL Rte 176	Albrecht Dr	SB	2	2	8	16	2		2					
IL Rte 176	Albrecht Dr	SB	2	3	8	24	3		3					
IL Rte 176	Albrecht Dr	SB	2	2	2	4	1		1					
IL Rte 176	Albrecht Dr	SB	2	3	8	24	3		3					
IL Rte 176	Albrecht Dr	SB	2	3	500	1500	167	167						
Albrecht Dr	IL Rte 176	NB	2	3	2200	6600	733	733						
Albrecht Dr	IL Rte 176	NB	2	4	8	32	4		4					
Albrecht Dr	IL Rte 176	NB	2	6	8	48	5			5				
Albrecht Dr	IL Rte 176	NB	2	2	6	12	1		1					
Albrecht Dr	IL Rte 176	NB	2	2	8	16	2		2					
Albrecht Dr	IL Rte 176	NB	2	2	8	16	2		2					
Albrecht Dr	IL Rte 176	NB	2	2	2	4	1		1					
Albrecht Dr	IL Rte 176	NB	2	1	6	6	1		1					
Albrecht Dr	IL Rte 176	NB	2	1	1	1	1		1					
Albrecht Dr	IL Rte 176	NB	2	3	150	450	50	50						
Albrecht Dr	IL Rte 176	NB	2	4	6	24	3		3					
IL Rte 176	Foster Ave	NB	2	3	1500	4500	500	500						
IL Rte 176	Foster Ave	NB	2	4	24	96	11			11				
IL Rte 176	Foster Ave	NB	2	2	24	48	5			5				
IL Rte 176	Foster Ave	NB	2	3	40	120	13			13				
IL Rte 176	Foster Ave	NB	2	12	8	96	11			11				
Foster Ave	Talbot Ave	NB	2	3	1600	4800	533	533						
Foster Ave	Talbot Ave	NB	2	4	8	32	4		4					
Foster Ave	Talbot Ave	NB	2	2	2	4	1		1					
TOTALS:								4249 SY	29 SY	122 SY		73 SY	4600 FT	92 EACH

FILE NAME = c:\projects\d136308\design_ea.dgn	USER NAME = bowerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 43

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	36

CONTRACT NO. 60E35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT