ROUTE: IL RTE 173 (Old Mill Creek Road to IL RTE 83)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Old Mill Creek Road	Total 20	WB	1,2	12	6	1440	160			160				
		W/B	1	4	14	56	6		6					
		WB	1	2	250	375	42	42						
		W/B	1	2	100	150	17	17						
		W/B	1	12	150	1800	200	200						
	TOTAL 14 EA	WB	1,2	6	12	72	112			112				
		EB	2	2	150	225	25	25						
		EB	RAMP	8	8	64	7			7				
		EB	1	2	100	150	17	17						
		EB	2	2	75	113	13	13						
		EB	1	6	18	108	12			12				
	HUNT CLUB ROAD	EB	2	8	100	800	89	89						
HUNT CLUB ROAD		WB	1	6	12	72	8			8				
		WB	1	12	15	180	20				20			
		CL	1	2	30	45	5			5				
	TOTAL 2 EA	WB	1	12	6	72	16			16				
		WB	1	2	50	75	8			8				
		WB	1	2	200	300	33	33						
		WB	1	2	100	150	17	17						
		WB	1	12	6	72	8			8				
		EB	C.L.	2	100	150	17	17						
		EB	1	12	25	300	33					33		
		WB	1	2	100	150	17	17						
		WB	1	12	25	300	33					33		
		WB	1	2	60	90	10	10						
		WB	1	6	60	360	40	40						
		WB	C.L.	2	200	300	33	30						
		WB	1	2	50	75	8	8						
		WB	1	12	6	72	8			8				
		WB	1	6	20	120	13			13				
		WB	1	2	100	150	17	17						
		EB	1	12	30	360	40					40		
		EB	1	2	100	150	17	17						
		EB	1	6	15	90	10			10				
		EB	1	8	50	400	44	44						
		C.L.	C.L	2	50	75	8	8						
		EB	1	12	20	240	27					27		
	US RTE 45	WB	1	2	100	150	17	17						
US RTE 45	TOTAL 10 EA	WB/EB	1	12	6	72	80			80				
	TOTAL 2 EA	WB/EB	1	12	8	96	21			21				
		EB	1	6	20	120	13			13				
	TOTAL 2 EA	C.L. & WB		2	100	150	33	33						
		WB	1	8	12	96	11			11				
		WB	1	4	12	48	5			5				
		EB	1	6	10	60	7			7				
	SAVAGE RD.TOT 4 EA	WB	SHLD	4	100	400	178	178						
SAVAGE RD	TOTAL 8 EA	WB/EB	1	12	6	72	64			64				
	TOTAL 2 EA	C.L. & WB		2	100	150	33	33						
	TOTAL 2 EA	WB	1	4	6	24	5			5				
	DEEP LAKE ROAD	W/B	SHLDR	4	200	800	89	89						
DEEP LAKE ROAD	TOTAL 12 EA	WB/EB	1	12	6	72	96			96				
	TOTAL 2 EA	WB/EB	SHLDR	4	100	400	89	89						
	IL RTE 83	C.L.	C.L.	2	100	150	17	17						
		TOTALS:						1117 SY		669 SY	20 SY	133 SY	2800 FT	60 EACH

FILE NAME = c:\projects\d136308\design_aa.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 173

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-009 PP	LAKE	85	65
		CONTRACT NO. 60E35		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT