ROUTE: Midlothian Road ( IL 176 to IL 22)

| CROSS STREETS FROM | CROSS STREETS TO | DIRECTION (EB/WB) (NB/SB) | LANE NO. (1, 2, 3) | PAVEMENT PATCH WIDTH | PAVEMENT PATCH LENGTH | REPAIR AREA (SQ FT) | REPAIR AREA (SQ YD) | MILL & RESURF | CLASS D PATCH TYPE I | CLASS D PATCH TYPE II | CLASS D PATCH TYPE III | CLASS D PATCH TYPE IV | PAVT MARKING 4" | RAISED REFL PAVT MKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| IL 176 | Hawley Street | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| Hawley Street | IL 60/83 | SB | | 4 | 12 | 48 | 5 | | | 5 | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | CL | 2 | 200 | 300 | 33 | 33 | | | | | | |
| | | SB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| IL 60/83 | Gilmer Road | SB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | LT E/P | 2 | 200 | 300 | 33 | 33 | | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 6 | 10 | 60 | 7 | | | 7 | | | | |
| | | SB | | 4 | 20 | 80 | 9 | | | 9 | | | | |
| | | SB | RT E/P | 2 | 200 | 300 | 33 | 33 | | | | | | |
| | | SB | CL | 2 | 200 | 300 | 33 | 33 | | | | | | |
| | | SB | | 4 | 10 | 40 | 4 | | 4 | | | | | |
| | | SB | RT E/P | 2 | 200 | 300 | 33 | 33 | | | | | | |
| Gilmer Road | Old McHenry Road | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 8 | 30 | 240 | 27 | | | | | 27 | | |
| | | SB | Rt Turn | 6 | 6 | 36 | 4 | | 4 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 12 | 25 | 300 | 33 | | | | | 33 | | |
| Old McHenry Road | Oakwood | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| Oakwood | IL 22 | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | SB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | | | | | | | | | | | | | |
| IL 22 | Oakwood | NB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | NB | | 12 | 25 | 300 | 33 | | | | | 33 | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| Oakwood | Old McHenry Road | NB | | 4 | 12 | 48 | 5 | | | 5 | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 100 | 400 | 44 | 44 | | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 12 | 50 | 600 | 67 | 67 | | | | | | |
| Old McHenry Road | Gilmer Road | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| Roberts Road | Darrel Road | NB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | NB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 12 | 48 | 5 | | | 5 | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 2 | 150 | 225 | 25 | 25 | | | | | | |
| Gilmer Road | IL 60/83 | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 10 | 40 | 4 | | 4 | | | | | |
| | | NB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | NB | | 4 | 6 | 24 | 3 | | 3 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | CL | 2 | 150 | 225 | 25 | 25 | | | | | | |
| IL 60/83 | Hawley Street | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | RT E/P | 2 | 150 | 225 | 25 | 25 | | | | | | |
| Hawley Street | IL 176 | NB | | 4 | 4 | 16 | 2 | | 2 | | | | | |
| | | NB | | 4 | 10 | 40 | 4 | | 4 | | | | | |
| | | NB | | 4 | 10 | 40 | 4 | | 4 | | | | | |
| | | | | | | | | 351 SY | 104 SY | 32 SY | | 93 SY | 1300 FT | 14 EACH |

| | | | |
|---|---|---|---|
| FILE NAME = c:\projects\d136308\design_ee.dgn | USER NAME = bauerdl | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 103.1218 ' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 3/13/2008 | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**PATCHING SCHEDULE**
**MIDLOTHIAN RD.**

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| VAR. | 2008-009 PP | LAKE | 85 | 73 |

CONTRACT NO. 60E35

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT