ROUTE: US 14 (IL 120 to Blue Jay Lane)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PVT MKS
ROUTE 120	BLUE JAY LANE	WB/NB	1	2.0	2.0	4.0	0		1					
ROUTE 120	BLUE JAY LANE	WB/NB	1	2.0	2.0	4.0	0		1					
ROUTE 120	1.1 HUGHES ROAD	WB/NB	1	2.0	2.0	4.0	0		1					
CENTERLINE JOINT 1.4 MILES		WB/NB	1	2.0	800.0	1600.0	178	178						
ROUTE 120	1.4 MILES	WB/NB	1	3.0	3.0	9.0	1			9				
ROUTE 120	1.4 MILES	WB/NB	1	2.0	2.0	4.0	0		1					
ROUTE 120	1.8 MILES	WB/NB	1	10.0	13.0	130.0	14			14				
CENTERLINE JOINT 1.8 MILES		WB/NB	1	2.0	600.0	1200.0	133	133						
ROUTE 120	1.8 MILES	WB/NB	1	6.0	6.0	36.0	4		4					
ROUTE 120	1.8 MILES	WB/NB	1	2.0	2.0	4.0	0		1					
ROUTE 120	1.8 MILES	WB/NB	1	2.0	2.0	4.0	0		1					
ROUTE 120	1.9 MILES	WB/NB	1	3.0	13.0	39.0	4		4					
CENTERLINE JOINT 1.9 MILES		WB/NB	1	2.0	1500.0	3000.0	333	333						
ROUTE 120	2.6 MILES	WB/NB	1	13.0	100.0	1300.0	144	144						
ROUTE 120	2.6 MILES	WB/NB	1	6.0	15.0	90.0	10			10				
CENTERLINE JOINT 2.6 MILES		WB/NB	1	2.0	1000.0	2000.0	222	222						
ROUTE 120	2.9 MILES	WB/NB	1	13.0	1000.0	13000.0	1444	1444						
CENTERLINE JOINT 3.0 MILES		WB/NB	1	2.0	1000.0	2000.0	222	222						
ROUTE 120	3.0 MILES	WB/NB	1	2.0	2.0	4.0	0		1					
ROUTE 120	3.3 DEEP CUT RD	WB/NB	1	3.0	6.0	18.0	2		2					
ROUTE 120	3.9 BUNKER HILL	WB/NB	1	3.0	6.0	18.0	2		2					
CENTERLINE JOINT 4.7 MILES		WB/NB	1	2.0	30.0	60.0	7	7						
ROUTE 120	7.0 MILES	WB/NB	1	6.0	13.0	78.0	9			9				
ROUTE 120	7.8 BLUE JAY ROAD	WB/NB	1											
BLUE JAY ROAD	RTE 120	EB/SB												
CENTERLINE JOINT .1 MILES		EB/SB	1	2.0	100.0	200.0	22	22						
CENTERLINE JOINT .3 MILES		EB/SB	1	2.0	200.0	400.0	44	44						
CENTERLINE JOINT .3 MILES		EB/SB	1	2.0	100.0	200.0	22	22						
CENTERLINE JOINT .3 MILES		EB/SB	1	2.0	50.0	100.0	11	11						
CENTERLINE JOINT .4 MILES		EB/SB	1	2.0	100.0	200.0	22	22						
BLUE JAY ROAD	1.3 MILES	EB/SB	1	6.0	15.0	90.0	10			10				
BLUE JAY ROAD	3.2 MILES	EB/SB	1	2.0	200.0	400.0	44	44						
BLUE JAY ROAD	4.1 MILES	EB/SB	1	6.0	13.0	78.0	9			9				
BLUE JAY ROAD	4.1 MILES	EB/SB	1	13.0	200.0	2600.0	289	289						
BLUE JAY ROAD	4.2 MILES	EB/SB	1	13.0	1000.0	13000.0	1444	1444						
BLUE JAY ROAD	4.9 MILES	EB/SB	1	13.0	1000.0	13000.0	1444	1444						
BLUE JAY ROAD	5.3 MILES	EB/SB	1	13.0	500.0	6500.0	722	722						
BLUE JAY ROAD	5.4 MILES	EB/SB	1	13.0	500.0	6500.0	722	722						
TOTALS:							7541 SY	7469 SY	19 SY	61 SY			FT	EACH

FILE NAME = c:\projects\d136108\design_ee.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
US 14

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-010 PP	MCHENRY	27	9
		CONTRACT NO. 60E36		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT