

CONTRACT NO. 60E37

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	15	15					
40600300	AGGREGATE (PRIME COAT)	TON	75	75					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1260	1260					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	2880	2880					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1500	1500					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2520	2520					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	29973	29973					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	8810	8810					
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SO YD	615	615					
44201353	CLASS C PATCHES, TYPE II, 10 INCH	SO YD	194	194					
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SO YD	683	683					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	2054	2054					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	1499	1499					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	3105	3105					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN 100% STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27250	27250					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1436	1436					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1436	1436					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	823	823					
X0324626	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 2 1/4"	SO YD	33	33					
* XX006058	POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	1340	1340					

\* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

PLOT DATE: 3/14/2008

3/14/2008 11:01:42 AM User:wjgreendp