ROUTE: US RTE 20 (WALNUT RD TO YORK RD)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	SURFACE TYPE (PCC/ASPHALT)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
WALNUT RD	YORK RD	EB	2	3	3	9	1	ASPHALT		1					
WALNUT RD	YORK RD	EB	2	4	4	16	2	ASPHALT		2					
WALNUT RD	YORK RD	EB	1	5	5	25	3	ASPHALT		3					
WALNUT RD	YORK RD	EB	2	3	3	9	1	ASPHALT		1					
WALNUT RD	YORK RD	EB	2	6	10	60	7	ASPHALT			7				
WALNUT RD	YORK RD	EB	2	7	6	42	5	ASPHALT			5				
WALNUT RD	YORK RD	EB	1	4	4	16	2	ASPHALT		2					
WALNUT RD	YORK RD	EB	1 & 2	4	4	16	2	ASPHALT		2					
WALNUT RD	YORK RD	EB	1 & 2	4	5	20	2	ASPHALT		2					
WALNUT RD	YORK RD	EB	2	12	2	24	3	ASPHALT		3					
WALNUT RD	YORK RD	EB	1	3	3	9	1	ASPHALT		2					
WALNUT RD	YORK RD	EB	2	12	4	48	5	ASPHALT			5				
WALNUT RD	YORK RD	EB	1	12	4	48	5	ASPHALT			5				
WALNUT RD	YORK RD	EB	1	12	8	96	11	ASPHALT			11				
WALNUT RD	YORK RD	EB	2	12	4	48	5	ASPHALT			5				
WALNUT RD	YORK RD	EB	1 & 2	1.5	1900	2850	317	PCC	317						
		TOTALS:					371 SY		317 SY	18 SY	38 SY			500 FT	46 EACH

FILE NAME = c:\projects\d136208\design_ea.dgn	USER NAME = wilgroendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE US 20	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-011 PP	DUPAGE	37	6
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E37		
	PLOT DATE = 3/14/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		