ROUTE: US 34 (I-355 to Belmont Ave)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	PAVT MARKING 12"	PAVT MARKING 24"	RAISED REFL PAVT MKS
CROSS	I-355	WB	2	10	40	400	44	44								
		WB	1	10	30	300	33					33				
		WB	1	11	20	220	24				24					
		WB	2	8	12	96	11			11						
		WB	1	8	10	80	9			9						
		WB	2	8	12	96	11			11						
		WB	2	8	12	96	11			11						
		WB	1	8	9	72	8			8						
	AUTORITY DRIVE	WB	1,2	22	30	660	73					73				
I-355	AUTHORITY DRIVE	EB	1,2	100	22	2200	244	244								
AUTHORITY	DRENDEL ROAD	EB	2	11	10	110	12			12						
		EB	2	11	30	330	37					37				
DRENDEL RD	CROSS	EB	2	10	60	600	67	67								
		EB	2	8	60	480	53	53								
		EB	2	8	9	72	8			8						
		EB	2	10	30	300	33					33				
		EB	2	10	20	200	22				22					
		EB	1,2	22	20	440	49					49				
BELMONT	CROSS ST	EB/WB	1,2,3													
Belmont	Cross street	WB	1	11	10	110	12			12						
		WB	2	15	8	120	13			13						
		EB	2	11	12	132	15			15						
		WB	1	11	30	330	37					37				
		WB	2	11	22	242	27				27					
		WB	2	11	34	374	42					42				
		WB	2	11	16	176	20				20					
		EB	2	22	16	352	39					39				
		EB	2	11	20	220	24				24					
		EB	2	11	8	88	10			10						
		EB	2	11	50	550	61	61								
		EB	2	11	20	220	24				24					
		EB	2	8	100	800	89	89								
		EB	2	11	60	660	73	73								
		EB	2	11	12	132	15			15						
CROSS	I-355	WB														
		WB	2	14	30	420	47					47				
CROSS	BELMONT	EB	2	11	12	132	15			15						
		EB	2	11	16	176	20				20					
AT CROSS	DEALER ENTRANCE	EB	2	10	40	400	44	44								
		TOTALS:					1376 SY	675 SY		150 SY	161 SY	390 SY	12700 FT	200 FT	100 FT	300 EACH

FILE NAME = c:\projects\d136208\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE US 34	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-011 PP	DUPAGE	37 / 9
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E37	
	PLOT DATE = 3/14/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	