ROUTE: IL 56 (I-355 to Lloyd Ave)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Esplanade	I355	EB	2	12	70	840	93	93						
Esplanade	I355	EB	3	12	45	540	60	60						
Esplanade	I355	EB	1	12	45	540	60	60						
Esplanade	I355	EB	2	12	25	300	33	33						
Esplanade	I355	EB	3	12	15	180	20				20			
Esplanade	I355	EB	3	12	15	180	20				20			
Esplanade	I355	EB	1	12	40	480	53	53						
Esplanade	I355	EB	3	12	45	540	60	60						
Esplanade	I355	EB	2	12	45	540	60	60						
Esplanade	I355	EB	2	12	25	30	33	33						
Esplanade	I355	EB	R turn	10	100	1000	111	111						
Esplanade	I355	EB	3	12	60	720	80	80						
Esplanade	I355	EB	3	12	200	2000	222	222						
Esplanade	I355	EB	3	12	50	600	67	67						
Esplanade	I355	EB	B joint	36	6	216	24				24			
I355	Esplanade	WB		1.5	60	90	10	10						
I355	Esplanade	WB		1.5	60	90	10	10						
I355	Esplanade	WB	2	12	50	600	67	67						
I355	Esplanade	WB	3	12	50	600	67	67						
I355	Esplanade	WB		1.5	1114	1671	186	186						
I355	Esplanade	WB	3	12	10	120	13	13						
I355	Esplanade	WB	2	12	6	72	8			8				
I355	Esplanade	WB	3	12	6	72	8			8				
I355	Esplanade	WB	3	12	70	840	93	93						
I355	Esplanade	WB	2	12	90	1080	120	120						
I355	Esplanade	WB	2	12	6	72	8			8				
I355	Esplanade	WB	3	12	6	72	8			8				
I355	Esplanade	WB	2	12	6	72	8			8				
I355	Esplanade	WB	3	12	6	72	8			8				
I355	Esplanade	WB	2	12	30	360	40	40						
Esplanade	Lloyd	WB	3	12	50	600	67	67						
Esplanade	Lloyd	WB	1	12	70	840	93	93						
Esplanade	Lloyd	WB	3	12	50	600	67	67						
Esplanade	Lloyd	WB	3	12	15	180	20				20			
Esplanade	Lloyd	WB	1	12	15	180	20				20			
Esplanade	Lloyd	WB	2	12	6	72	8			8				
Esplanade	Lloyd	WB	3	12	6	72	8			8				
Esplanade	Lloyd	WB	L turn	12	300	3600	400	400						
Esplanade	Lloyd	WB	L turn	12	300	3600	400	400						
Esplanade	Lloyd	WB	1	12	100	1200	133	133						
Esplanade	Lloyd	WB	3	12	100	1200	133	133						
TOTALS:							3000 SY	2832 SY		64 SY	104 SY		FT	EACH

FILE NAME = c:\projects\d136208\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 183.7851 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 56

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-011 PP	DUPAGE	37	16

CONTRACT NO. 60E37

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT