ROUTE: Hibbard Rd (Lake Ave to Winnetka Rd)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Walden		"	"	4	6	24	3		3					
	Country	"	"	8	6	48	5		5					
Country		"	"	8	40	320	36					36		
	Cranston	"	"	5	30	150	17				17			
Cranston		"	"	12	30	360	40	40						
		"	"	12	15	180	20				20			
		"	"	8	25	200	22				22			
	Lake	"	"	5	150	750	83	83						
Lake		"	"	12	6	72	8			8				
		"	"	1.5	125	187.5	21				21			
		"	"	12	8	96	11			11				
		"	"	4	15	60	7			7				
		"	"	12	30	360	40	40						
		"	"	12	40	480	53	53						
		"	"	8	10	80	9			9				
Skokie		CL	CL	1.5	10	15	2		2					
	Lake	"	"	1.5	10	15	2		2					
Lake	Melrose	"	"	1.5	10	15	2		2					
Melrose	Cranston	"	"	1.5	20	30	3		3					
Cranston	Country	"	"	1.5	10	15	2		2					
Country		"	"	1.5	20	30	3		3					
	Waldon	"	"	1.5	10	15	2		2					
Waldon		"	"	1.5	15	22.5	3		3					
		"	"	1.5	40	60	7			7				
		"	"	1.5	20	30	3		3					
		"	"	1.5	15	22.5	3		3					
		"	"	1.5	60	90	10			10				
		"	"	1.5	20	30	3		3					
		"	"	1.5	10	15	2		2					
	Illinois	"	"	1.5	30	45	5		5					
		Total					2040 SY	1208 SY	99 SY	209 SY	184 SY	347 SY	1000 FT	50 EACH

FILE NAME = c:\projects\d136528\design_aa.dgn	USER NAME = bauerd1	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
HIBBARD RD.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-014 PP	COOK	84	48

CONTRACT NO. 60E40

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT