

ROUTE: Lincoln Ave (Devon Ave to Carpenter)

CROSS STREETS		DIRECTION (EB/WB (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
Devon		NWB	1	12	1	12	1		1					
	Monticello	"	2	12	3	36	4		4					
Monticello	Arthur	"	1	12	2	24	3		3					
Arthur		"	1	12	3	36	4		4					
	R R track	"	1	6	10	60	7			7				
R R track		"	2	5	5	25	3		3					
	Avers	"	1	3	4	12	1		1					
Springfield		"	1	12	2	24	3		3					
		"	2	3	4	12	1		1					
		"	2	3	15	45	5		5					
	Harding	"	2	6	8	48	5		5					
Crawford	Pratt	"	1	3	4	12	1		1					
Pratt		"	1	6	10	60	7			7				
	Keystone	"	2	6	8	48	5		5					
Keystone	Karlov	"	1	12	2	24	3		3					
Karlov		"	1	6	10	60	7			7				
	Morse	"	2	6	6	36	4		4					
Morse	Kedvale	"	2	2	6	12	1		1					
Kedvale		"	1	12	6	72	8			8				
	Keeler	"	2	6	8	48	5		5					
Keeler		"	1	6	4	24	3		3					
		"	1	4	75	300	33					33		
	Tripp	"	2	1.5	45	67.5	8			8				
Tripp		"	1&2	1.5	10	15	2		2					
		"	1&2	1.5	30	45	5		5					
		"	1	6	3	18	2		2					
		"	1	3	3	9	1		1					
		"	1&2	1.5	10	15	2		2					
		"	1&2	1.5	6	9	1		1					
		"	2	1.5	16	24	3		3					
		"	1	3	2	6	1		1					
	Kostner	"	1	12	2	24	3		3					
Chase		"	2	1.5	20	30	3		3					
	Jarvis	"	1&2	1.5	8	12	1		1					
Jarvis	Skokie Blvd	"	1&2	1.5	10	15	2		2					
Skokie Blvd	Howard	"	1&2	1.5	220	330	37					37		
		"	2	3	30	90	10			10				
		"	1&2	1.5	10	15	2		2					
		"	1	12	20	240	27					27		
		"	1&2	1.5	10	15	2		2					
		"	2	3	10	30	3		3					
		"	1&2	1.5	20	30	3		3					
	Brummel	"	2	6	8	48	5		5					
Brummel		"	1&2	1.5	6	9	1		1					
	Niles	"	1&2	1.5	75	112.5	13			13				
Niles		"	1&2	1.5	80	120	13			13				
		"	1&2	1.5	8	12	1		1					
		"	2	8	8	64	7			7				
		"	1	12	4	48	5		5					
	Mulford	"	2	6	2	12	1		1					
		"	1&2	1.5	8	12	1		1					
Leclaire		"	1&2	1.5	20	30	3		3					
		"	1&2	1.5	10	15	2		2					
		"	1&2	1.5	6	9	1		1					
		"	1	12	6	72	8			8				
		"	1&2	1.5	20	30	3		3					
	Babb	"	1&2	1.5	5	7.5	1		1					

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\dl36588\design_ee.dgn	USER NAME = beuerd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE LINCOLN AVE.				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	2008-014 PP	COOK	84	57
		CHECKED -	REVISED -		CONTRACT NO. 60E40									
		DATE -	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT									