ROUTE: Lincoln Ave (Devon Ave to Carpenter)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Carpenter		SEB	1&2	1.5	20	30	3		3					
	Claire	"	1	12	15	180	20				20			
Claire		"	1	12	4	48	5		5					
		"	1	12	10	120	13			13				
	Mulford	"	2	6	20	120	13			13				
Mulford		"	1&2	1.5	10	15	2		2					
		"	1&2	1.5	20	30	3		3					
		"	1	12	30	360	40	40						
		"	1&2	1.5	75	112.5	13			13				
	Harvard	"	1	12	16	192	21				21			
Harvard		"	1	12	4	48	5		5					
		"	1&2	1.5	18	27	3		3					
		"	2	3	8	24	3		3					
		"	1&2	1.5	8	12	1		1					
		"	2	4	4	16	2		2					
		"	1	2	6	12	1		1					
	Brummel	"	1&2	1.5	20	30	3		3					
Brummel		"	2	8	10	80	9			9				
		"	2	12	45	540	60	60						
	Dobson	"	1&2	1.5	6	9	1		1					
Dobson		"	1&2	1.5	10	15	2		2					
		"	2	12	12	144	16				16			
		"	2	12	15	180	20				20			
	Howard	"	1&2	1.5	4	6	1		1					
Howard	Skokie	"	1&2	1.5	15	22.5	3		3					
Skokie		"	1&2	1.5	15	22.5	3		3					
	Jarvis	"	1&2	1.5	15	22.5	3		3					
Jarvis		"	2	1.5	80	120	13			13				
		"	1	3	3	9	1		1					
		"	LT&1	1.5	25	37.5	4		4					
	Chase	"	LT&1	1.5	20	30	3		3					
Kostner		"	1	4	10	40	4		4					
	Tripp	"	1	1.5	20	30	3		3					
Tripp		"	1	12	4	48	5		5					
		"	2	4	30	120	13			13				
		"	2	1.5	15	22.5	3		3					
		"	1	4	10	40	4		4					
		"	1	2	2	4	0							
	Morse	"	1	1.5	18	27	3		3					
Kedvale		"	1	2	2	4	0							
	Pratt	"	1	2	6	12	1		1					
Pratt	Crawford	"	2	3	3	9	1		1					
Harding		"	1	3	8	24	3		3					
	Springfield	"	1	4	6	24	3		3					
Springfield		"	1&2	1.5	4	6	1		1					
		"	2	1.5	8	12	1		1					
	R R track	"	2	1.5	10	15	2		2					
R R track		"	1	12	2	24	3		3					
	Hamlin	"	2	12	6	72	8			8				
Arthur		"	1	4	2	8	1		1					
	Devon	"	1	2	2	4	0							
		Total					648 SY	100 SY	202 SY	170 SY	77 SY	97 SY	700 FT	35 EACH

FILE NAME = c:\projects\d136508\design_ea.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
LINCOLN AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-014 PP	COOK	84	58
		CONTRACT NO. 60E40		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT