ROUTE: Milwaukee Ave (Dearlove Rd to Sanders Rd)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Deer Love	West Lake	NB	2	1.5	150	225	25				25			
				5	12	60	7			7				
				5	12	60	7			7				
				1.5	500	750	83	83						
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				3	200	600	67	67						
				4	200	800	89	89						
				5	500	2500	278	278						
				6	12	72	8			8				
				6	500	3000	333	333						
				12	300	3600	400	400						
				5	12	60	7			7				
				5	12	60	7			7				
				5	200	1000	111	111						
				3	400	1200	133	133						
				5	200	1000	111	111						
West Lake	Sanders	NB	2	1.5	50	75	8			8				
West Lake	Deer Love	SB	2	5	10	50	6			6				
				1.5	20	30	3		3					
				6	12	72	8			8				
				6	12	72	8			8				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				1.5	500	750	83	83						
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				1.5	100	150	17				17			
Deer Love	West Lake	NB	1	1.5	400	600	67	67						
				5	12	60	7			7				
				4	15	60	7			7				
				5	20	100	11			11				
				5	12	60	7			7				
				5	150	750	83	83						
				6	50	300	33					33		
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				1.5	20	30	3		3					
Sanders	West Lake	SB	1	10	12	120	13			13				
West Lake	Deer Love	SB	1	8	15	120	13			13				
				5	30	150	17				17			
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
				5	40	200	22				22			
				6	15	90	10			10				
				5	12	60	7			7				
				6	12	72	8			8				
				5	12	60	7			7				
				5	12	60	7			7				
				5	25	125	14			14				
				5	12	60	7			7				
				5	12	60	7			7				
				5	12	60	7			7				
		Total					2307 SY	1838 SY	6 SY	359 SY	81 SY	33 SY	2100 FT	100 EACH

FILE NAME = c:\projects\d136508\design_aa.dgn	USER NAME = bauerdl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 183.1218 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/13/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
MILWAUKEE AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-014 PP	COOK	84	59

CONTRACT NO. 60E40

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT