ROUTE: Archer Ave (Cicero Ave to Hunt Ave)

CROSS STREETS FROM	TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Cicero Ave	Hunt Ave	EB	1	1	1	1	0							
Cicero Ave	Hunt Ave	EB	1	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	10	20	200	22				22			
Cicero Ave	Hunt Ave	EB	1	2	2	4	0							
Cicero Ave	Hunt Ave	WB	2	2	2	4	0							
Cicero Ave	Hunt Ave	EB	2	1	1	1	0							
Cicero Ave	Hunt Ave	EB	1	1	1	1	0							
Cicero Ave	Hunt Ave	EB	2	2	1	2	0							
Cicero Ave	Hunt Ave	EB	2	2	1	2	0							
Cicero Ave	Hunt Ave	WB	1	1	3	3	0							
Cicero Ave	Hunt Ave	WB	2	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	4	4	16	2		2					
Cicero Ave	Hunt Ave	WB	2	1	3	3	0							
Cicero Ave	Hunt Ave	WB	2	1	1	1	0							
Cicero Ave	Hunt Ave	WB	1	1	1	1	0							
Cicero Ave	Hunt Ave	WB	1	1	1	1	0							
Cicero Ave	Hunt Ave	WB	1	1	1	1	0							
Cicero Ave	Hunt Ave	WB	1	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	6	15	90	10			10				
Cicero Ave	Hunt Ave	WB	1	2	20	30	3		3					
Cicero Ave	Hunt Ave	WB	2	2	2	4	0							
Cicero Ave	Hunt Ave	WB	2	2	2	4	0							
Cicero Ave	Hunt Ave	WB	2	2	2	3	0							
Cicero Ave	Hunt Ave	WB	2	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	1	1	1	0							
Cicero Ave	Hunt Ave	WB	2	1	2	2	0							
Cicero Ave	Hunt Ave	WB	1	1	1	1	0							
Cicero Ave	Hunt Ave	WB	1	1	2	2	0							
Cicero Ave	Hunt Ave	WB	1	1	1	1	0							
		Total					43 SY	0 SY	5 SY	10 SY	22 SY	0 SY	100 FT	10 EACH

20

FILE NAME = c:\projects\d136008\design_aa.dgn	USER NAME = smithkl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/14/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
ARCHER AVE.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-015 PP	COOK	75	26

CONTRACT NO. 60E41

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT