

ROUTE: Mannheim Rd (I-290 to St Charles Rd; Lake St to Grand Ave)

CROSS STREETS		DIRECTION (EB/WB NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
Wilcox	Structure	NB	2	4	4		2							
Wilcox		NB	1	12	40		53	53						
Washington	Structure	NB	1,2	24	300		800	800						
Randolph		NB	2	4	4		2		2					
Randolph		NB	2	4	4		2		2					
St Charles		NB	2	4	4		2		2					
Twining	Structure	SB	2	4	2		1		1					
Twining		SB	2	4	2		1		1					
Aldi		SB	2	3	3		1		1					
Aldi		SB	2	3	3		1		1					
Randolph		SB	2	4	60		27				27			
Randolph		SB	2	4	4		2		2					
Washington		SB	1,2	24	200		533	533						
Warner		SB	2	4	4		2		2					
Warner		SB	2	4	4		2		2					
Madison		SB	2	4	4		2		2					
Madison		SB	1,2	24	3		8			8				
Lake St		NB	2	12	20	240	27					27		
		NB	3	4	4	16	2		2					
		NB	2	12	4	48	5		5					
		NB	3	12	10	120	13			13				
		NB	2	4	4	16	2		2					
		NB	3	4	4	16	2		2					
Soffel Ave	Soffel Ave	NB	2	12	5	60	7			7				
		NB	3	4	4	16	2		2					
		NB	2	12	4	48	5		5					
		NB	3	12	4	48	5		5					
		NB	3	12	4	48	5		5					
		NB	1	12	4	48	5		5					
		NB	3	6	6	36	4		4					
		NB	3	6	10	60	7			7				
		NB	3	12	4	48	5		5					
		NB	1	12	4	48	5		5					
		NB	3	12	15	180	20				20			
		NB	1	3	8	24	3		3					
Soffel Ave (con't)		NB	3	12	10	120	13			13				
		NB	3	12	4	48	5		5					
		NB	3	12	4	48	5		5					
		NB	3	12	5	60	7			7				
Armitage	Armitage	NB	1	12	10	120	13			13				
		NB	1	12	10	120	13			13				
		NB	2	12	10	120	13			13				
		NB	3	12	10	120	13			13				
		NB	3	12	5	60	7			7				
		NB	3	6	8	48	5		5					
		NB	2	12	4	48	5		5					
		NB	3	4	4	16	2		2					
		NB	3	12	8	96	11			11				
		NB	3	4	3	12	1		1					
		NB	3	12	5	60	7			7				
		NB	2	12	5	60	7			7				
		NB	1	12	5	60	7			7				
		NB	1	12	5	60	7			7				
Armitage (con't)		NB	1	4	4	16	2		2					
	Fullerton Ave	NB	1	4	4	16	2		2					
Fullerton Ave		NB	3	12	4	48	5		5					
		NB	2	12	4	48	5		5					
		NB	3	12	4	48	5		5					
		NB	2	12	4	48	5		5					
		NB	1	12	4	48	5		5					
		NB	3	12	6	72	8			8				
		NB	2	12	6	72	8			8				
		NB	2	4	5	20	2		2					
	Wrightwood	NB	3	12	4	48	5		5					

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\dl3668\design_00.dgn	USER NAME = mm1	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE MANHEIM RD	F.A.P. RTE. VAR.	SECTION 2008-015 PP	COUNTY COOK	TOTAL SHEETS 75	SHEET NO. 42		
PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/14/2008	DATE -	REVISED -										