

ROUTE: 17th Ave (Harvard St to 22nd St)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
HARVAD	FILMORE	SB	1	6	550	3300	367	367						
HARVAD	FILMORE	SB	1	18	3	54	6			6				
HARVAD	FILMORE	SB	1	18	3	54	6			6				
HARVAD	FILMORE	SB	1	18	6	108	12			12				
HARVAD	FILMORE	SB	1	12	5	60	7			7				
FILMORE	ROOSENT	SB	1	8	100	800	89	89						
FILMORE	ROOSENT	SB	1	8	50	400	44	44						
FILMORE	ROOSENT	SB	1	12	2	24	3		3					
FILMORE	ROOSENT	SB	1	18	2	36	4		4					
FILMORE	ROOSENT	SB	1	18	2	36	4		4					
ROOSENT	13th	SB	1	3	20	60	7			7				
ROOSENT	13th	SB	1	12	3	36	4		4					
ROOSENT	13th	SB	1	3	20	60	7			7				
13th	14th	SB	1	3	60	180	20				20			
13th	14th	SB	1	12	10	120	13			13				
13th	14th	SB	1	12	20	240	27					27		
13th	14th	SB	2	12	6	72	8			8				
13th	14th	SB	2	6	6	36	4	4						
14th	15th	SB	2	12	10	120	13			13				
14th	15th	SB	1 & 2	24	10	240	27					27		
14th	15th	SB	2	12	5	60	7			7				
15th	CENTRAL DR	SB	1 & 2	24	30	720	80	80						
TRACKS	TRACKS	SB	1 & 2	24	20	480	53	53						
TRACKS	TRACKS	SB	1 & 2	24	20	480	53	53						
TRACKS	22nd	SB	1 & 2	24	2	48	5		5					
TRACKS	22nd	SB	1 & 2	24	2	48	5		5					
TRACKS	22nd	SB	1	12	6	72	8			8				
TRACKS	22nd	SB	2	12	6	72	8			8				
TRACKS	22nd	SB	1	24	10	240	27					27		
22nd	TRACKS	NB	1 & 2	24	2	48	5		5					
22nd	TRACKS	NB	1 & 2	24	2	48	5		5					
22nd	TRACKS	NB	1 & 2	24	5	120	13			13				
22nd	TRACKS	NB	1 & 2	24	3	72	8			8				
22nd	TRACKS	NB	1 & 2	24	3	72	8			8				
22nd	TRACKS	NB	2	12	6	72	8			8				
22nd	TRACKS	NB	2	6	12	72	8			8				
TRACKS	TRACKS	NB	1 & 2	24	20	480	53	53						
TRACKS	TRACKS	NB	1 & 2	24	20	480	53	53						
CENTRAL	15th	NB	1	12	2	24	3		3					
CENTRAL	15th	NB	2	6	4	24	3		3					
CENTRAL	15th	NB	1	12	20	240	27					27		
CENTRAL	15th	NB	2	12	50	600	67	67						
CENTRAL	15th	NB	1	12	50	600	67	67						
15th	14th	NB	2	12	2	24	3		3					
15th	14th	NB	1	12	2	24	3		3					
15th	14th	NB	1	12	50	600	67	67						
15th	14th	NB	1	12	3	36	4		4					
15th	14th	NB	1	12	60	720	80	80						
15th	14th	NB	2	12	4	48	5		5					
15th	14th	NB	1	12	60	720	80	80						
15th	14th	NB	2	24	2	48	5		5					
15th	14th	NB	1	10	10	100	11			11				
14th	13th	NB	2	6	10	60	7			7				
14th	13th	NB	1 & 2	24	10	240	27					27		
14th	13th	NB	1	6	60	360	40	40						
14th	13th	NB	1	4	200	800	89	89						
14th	13th	NB	2	4	4	16	2		2					
14th	13th	NB	1 & 2	12	2	24	3		3					
13th	ROOSEVELT	NB	1	24	2	48	5		5					
13th	ROOSEVELT	NB	1	2	200	400	44	44						
ROOSEVELT	FILLMORE	NB	2	3	3	9	1		1					
ROOSEVELT	FILLMORE	NB	1 & 2	18	3	54	6			6				
ROOSEVELT	FILLMORE	NB	1 & 2	18	2	36	4		4					
ROOSEVELT	FILLMORE	NB	1 & 2	18	2	36	4		4					
FILLMORE	HARVAD	NB	2	2	2	4	0		1					
FILLMORE	HARVAD	NB	1 & 2	12	20	240	27					27		
FILLMORE	HARVAD	NB	1	12	6	72	8			8				

Total 1770 SY 1326 SY 85 SY 179 SY 20 SY 162 SY 800 FT 40 EACH

FILE NAME =	USER NAME = smj.chk1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE 17TH AVE.			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca:\projects\1037051\design_ee.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	COOK	75	57
		CHECKED -	REVISED -								CONTRACT NO.	60E41	
		DATE -	REVISED -								FED. ROAD DIST. NO. 1 (ILLINOIS) FED. AID PROJECT		