

ROUTE: 22nd St/Cermak Rd (Des Plaines Ave to Westchester Blvd)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
Top of Bridge 25th Ave	Suffolk	WB	2	12	20	240	27					27		
Top of Bridge 25th Ave	Suffolk	WB	1,2	24	4	96	11			11				
Top of Bridge 25th Ave	Suffolk	WB	2	12	10	120	13			13				
Top of Bridge 25th Ave	Suffolk	WB	2	12	10	120	13			13				
Top of Bridge 25th Ave	Suffolk	WB	1	10	10	100	11			11				
Top of Bridge 25th Ave	Suffolk	WB	1	12	20	240	27					27		
Top of Bridge 25th Ave	Suffolk	WB	1	5	5	25	3		3					
Top of Bridge 25th Ave	Suffolk	WB	1	12	30	360	40	40						
Suffolk	Suffolk	WB	2	12	3	36	4		4					
Suffolk	Hill	WB	2	12	5	60	7			7				
Suffolk	Hill	WB	1	12	20	240	27					27		
Suffolk	Hill	WB	1	12	10	120	13			13				
Suffolk	Hill	WB	2	5	10	50	6			6				
Hill	Weschester	WB	1,2	5	90	450	50	50					30	4
Hill	Weschester	WB	1,2	5	150	750	83	83					50	6
Hill	Weschester	WB	2	12	10	120	13			13				
Hill	Weschester	WB	2	5	5	25	3		3					
Manhiem	Top Of Bridge	EB	1	12	30	360	40	40						
Manhiem	Top Of Bridge	EB	1,2	24	2	48	5		5					
Manhiem	Top Of Bridge	EB	1	10	12	120	13			13				
Manhiem	Top Of Bridge	EB	1,2	24	3	72	8			8				
Manhiem	Top Of Bridge	EB	2	12	3	36	4		4					
Manhiem	Top Of Bridge	EB	2	3	3	9	1		1					
Manhiem	Top Of Bridge	EB	1	5	5	25	3		3					
Manhiem	Top Of Bridge	EB	1	12	10	120	13			13				
Manhiem	Top Of Bridge	EB	1	24	3	72	8			8				
Manhiem	Top Of Bridge	EB	1	6	30	180	20				20			
Manhiem	Top Of Bridge	EB	2	12	4	48	5		5					
Manhiem	Top Of Bridge	EB	2	12	2	24	3		3					
Manhiem	Top Of Bridge	EB	2	10	100	1000	111	111						
Manhiem	Top Of Bridge	EB	2	12	20	240	27					27		
Manhiem	Top Of Bridge	EB	2	5	5	25	3		3					
Manhiem	Top Of Bridge	EB	2	12	10	120	13			13				
Manhiem	Top Of Bridge	EB	1,2	24	3	72	8			8				
Manhiem	Top Of Bridge	EB	1,2	24	4	96	11			11				
Manhiem	Top Of Bridge	EB	1	12	4	48	5		5					
Top Of Bridge	Terry Lane	EB	1,2	5	350	1750	194	194						
Top Of Bridge	Terry Lane	EB	1,2	5	1000	5000	556	556						
Top Of Bridge	Terry Lane	EB	1	12	5	60	7			7				
Top Of Bridge	Terry Lane	EB	2	12	25	300	33	33						
Top Of Bridge	Terry Lane	EB	1,2	24	4	96	11			11				
Top Of Bridge	Terry Lane	EB	1,2	24	4	96	11			11				
Top Of Bridge	Terry Lane	EB	1	12	15	180	20				20			
Top Of Bridge	Terry Lane	EB	2	12	10	120	13			13				
Top Of Bridge	Terry Lane	EB	1,2	24	2	48	5		5					
Top Of Bridge	Terry Lane	EB	1,2	24	2	48	5		5					
Terry Lane	17th ave	EB	2	10	60	600	67	67						
Left Turn Lane	Left Turn Lane	EB	1	12	20	240	27					27		
Terry Lane	17th ave	EB	1	12	20	240	27					27		
Terry Lane	17th ave	EB	1	5	5	25	3		3					
17th ave	14th ave	EB	1	12	2	24	3		3					
17th ave	14th ave	EB	1	3	40	120	13			13				
17th ave	14th ave	EB	2	10	12	120	13			13				
14th ave	14th ave	EB	2	10	10	100	11			11				
14th ave	13th ave	EB	1,2	5	120	600	67	67						
14th ave	13th ave	EB	1,2	24	3	72	8			8				

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\136608\design-ee.dgn	USER NAME = smthkl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PATCHING SCHEDULE 22ND ST. (CERMAK RD.)</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 103.7851' / IN.	DRAWN -	REVISED -	VAR.			2008-015 PP	COOK	75	53	
PLOT DATE = 3/14/2008	CHECKED -	REVISED -	CONTRACT NO. 60E41							
	DATE -	REVISED -	FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT							
SCALE:		SHEET NO. OF SHEETS		STA. TO STA.						