ROUTE: IL 83 (IL 171/Archer Ave to 104th Ave)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Archer	Equestrian Woods	SB	1	12	6	72	8			8				
Archer	Equestrian Woods	SB	1	6	6	36	4		4					
Archer	Equestrian Woods	SB	1	12	6	72	8			8				
Archer	Equestrian Woods	SB	1	12	6	72	8			8				
Archer	Equestrian Woods	SB	1	6	20	120	13			13				
Archer	Equestrian Woods	SB	RTL	12	40	480	53	53						
Archer	Equestrian Woods	SB	RTL	12	100	1200	133	133						
Equestrian Woods	104th	SB	1	6	20	120	13			13				
Equestrian Woods	104th	SB	1	6	20	120	13			13				
Equestrian Woods	104th	SB	1	6	20	120	13			13				
Equestrian Woods	104th	SB	1	6	300	1800	200	200						
Equestrian Woods	104th	SB	1	3	40	120	13			13				
Equestrian Woods	104th	SB	1	12	6	72	8			8				
Equestrian Woods	104th	SB	1	6	10	60	7			7				
Equestrian Woods	104th	SB	1	6	20	120	13			13				
Equestrian Woods	104th	SB	1	6	25	150	17				17			
Equestrian Woods	104th	SB	1	6	20	120	13			13				
Equestrian Woods	104th	SB	1	12	200	2400	267	267						
Equestrian Woods	104th	SB	1	12	100	1200	133	133						
Equestrian Woods	104th	SB	1	12	6	72	8			8				
Equestrian Woods	104th	SB	1	12	160	1920	213	213						
104th	Woodview Ln	NB	1	6	10	60	7			7				
104th	Woodview Ln	NB	1	12	80	960	107	107						
104th	Woodview Ln	NB	1	12	560	6720	747	747						
104th	Woodview Ln	NB	1	12	150	1800	200	200						
104th	Woodview Ln	NB	1	6	50	300	33					33		
104th	Woodview Ln	NB	1	6	40	240	27					27		
104th	Woodview Ln	NB	1	6	40	240	27					27		
104th	Woodview Ln	NB	1	3	20	60	7			7				
104th	Woodview Ln	NB	1	3	20	60	7			7				
104th	Woodview Ln	NB	1	3	20	60	7			7				
104th	Woodview Ln	NB	1	6	40	240	27					27		
104th	Woodview Ln	NB	1	6	6	36	4		4					
104th	Woodview Ln	NB	1	6	6	36	4		4					
104th	Woodview Ln	NB	1	3	80	240	27					27		
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	6	50	300	33					33		
104th	Woodview Ln	NB	1	6	6	36	4		4					
104th	Woodview Ln	NB	1	6	6	36	4		4					
104th	Woodview Ln	NB	1	6	6	36	4		4					
104th	Woodview Ln	NB	1	6	6	36	4		4					
104th	Woodview Ln	NB	1	12	6	72	8			8				
104th	Woodview Ln	NB	1	12	6	72	8			8				
Woodview Ln	171	NB	1	6	6	36	4		4					
Woodview Ln	171	NB	1	6	6	36	4		4					
Woodview Ln	171	NB	1	6	6	36	4		4					
Woodview Ln	171	NB	1	6	6	36	4		4					
Woodview Ln	171	NB	1	12	6	72	8			8				
Woodview Ln	171	NB	1	12	6	72	8			8				
Woodview Ln	171	NB	1	6	6	36	4		4					
		Total					2538 SY	2053 SY	48 SY	246 SY	17 SY	174 SY	7500 FT	0 EACH

52

FILE NAME = c:\projects\d136708\design_ee.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 83

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-016 PP	COOK	131	23

CONTRACT NO. 60E42

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT