

ROUTE: Dixie Hwy (Ashland Ave to IL 1)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
Ashland	Joe Orr	SB	2	6	12	72	8			8				
Ashland	Joe Orr	SB	2	6	12	72	8			8				
Ashland	Joe Orr	SB	2	12	50	600	67	67						
Ashland	Joe Orr	SB	2	6	6	36	4		4					
Ashland	Joe Orr	SB	2	Joint	200	0	0							
Ashland	Joe Orr	SB	2	6	12	72	8			8				
Ashland	Joe Orr	SB	2	Joint	200	0	0							
Joe Orr	10th St	SB	2	6	12	72	8			8				
Joe Orr	10th St	SB	2	6	12	72	8			8				
Joe Orr	10th St	SB	2	6	12	72	8			8				
Joe Orr	10th St	SB	2	Joint	200	0	0							
10th	Rte 1	SB	2	12	12	144	16				16			
Rte 1	10th	NB	2	6	20	120	13			13				
10th	Joe Orr	NB	2	6	12	72	8			8				
10th	Joe Orr	NB	2	6	12	72	8			8				
10th	Joe Orr	NB	2	12	12	144	16				16			
10th	Joe Orr	NB	2	6	12	72	8			8				
10th	Joe Orr	NB	2	12	150	1800	200	200						
10th	Joe Orr	NB	2	6	12	72	8			8				
10th	Joe Orr	NB	2	6	12	72	8			8				
10th	Joe Orr	NB	2	6	12	72	8			8				
10th	Joe Orr	NB	2	6	12	72	8			8				
Joe Orr	Ashland	NB	2	6	6	36	4		4					
Joe Orr	Ashland	NB	2	6	12	72	8			8				
Joe Orr	Ashland	NB	2	12	24	288	32				32			
Joe Orr	Ashland	NB	2	Joint	200	0	0							
Joe Orr	Ashland	NB	2	12	12	144	16				16			
Joe Orr	Ashland	NB	2	6	12	72	8			8				
Joe Orr	Ashland	NB	2	12	30	360	40	40						
Joe Orr	Ashland	NB	2	6	6	36	4		4					
Joe Orr	Ashland	NB	2	6	12	72	8			8				
Ashland	Joe Orr	SB	1	6	12	72	8			8				
Ashland	Joe Orr	SB	1	6	6	36	4		4					
Ashland	Joe Orr	SB	1	12	40	480	53	53						
Ashland	Joe Orr	SB	1	6	50	300	33				33			
Ashland	Joe Orr	SB	1	12	12	144	16				16			
Ashland	Joe Orr	SB	1	6	12	72	8			8				
Ashland	Joe Orr	SB	1	6	12	72	8			8				
Ashland	Joe Orr	SB	1	6	12	72	8			8				
Ashland	Joe Orr	SB	1	6	40	240	27				27			
Ashland	Joe Orr	SB	1	4	30	120	13			13				
Joe Orr	Rte 1	SB	1	6	12	72	8			8				
Joe Orr	Rte 1	SB	1	6	12	72	8			8				
Rte 1	10th	NB	1	6	12	72	8			8				
Rte 1	10th	NB	1	6	12	72	8			8				
10th	Joe Orr	NB	1	6	12	72	8			8				
10th	Joe Orr	NB	1	6	12	72	8			8				
10th	Joe Orr	NB	1	6	12	72	8			8				
10th	Joe Orr	NB	1	6	6	36	4		4					
10th	Joe Orr	NB	1	6	6	36	4		4					
Joe Orr	Ashland	NB	1	6	12	72	8			8				
Joe Orr	Ashland	NB	1	6	12	72	8			8				
Joe Orr	Ashland	NB	1	6	12	72	8			8				
Joe Orr	Ashland	NB	1	6	12	72	8			8				
Joe Orr	Ashland	NB	1	12	12	144	16				16			
Joe Orr	Ashland	NB	1	6	12	72	8			8				

Total
847 SY 360 SY 24 SY 290 SY 80 SY 92 SY **475** FT **48** EACH

FILE NAME = c:\projects\136708\design_00.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE DIXIE HIGHWAY	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 1/8" = 1' / IN.	CHECKED -	REVISED -	VAR.			2008-016 PP	COOK	131	45		
PLOT DATE = 3/15/2008	DATE -	REVISED -	SCALE:			SHEET NO.	OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT
										CONTRACT NO. 60E42	