

ROUTE: Glenwood Dyer Rd & Glenwood Rd

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
FROM	TO													
Glenwood Dyer Rd (Burnham Ave to Cottage Grove Ave)														
Burnham	Torrence	WB	1	6	12	72	8			8				
Torrence	IL 394	WB	1	6	12	72	8			8				
Torrence	IL 394	WB	1	6	6	36	4		4					
IL 394	Cottage Grove	WB	1	6	6	36	4		4					
Glenwood/Lansing	Cottage Grove	EB	1	6	12	72	8			8				
Glenwood/Lansing	Cottage Grove	EB	1	6	6	36	4		4					
Cottage Grove	Stoney Island	EB	1	6	6	36	4		4					
Stoney Island	Torrence	EB	1	6	6	36	4		4					
Stoney Island	Torrence	EB	1	6	12	72	8			8				
wood Rd (Holbrook Rd to IL 1)														
Holbrook	Rte 1	SB	1	6	12	72	8			8				
Holbrook	Rte 1	SB	1	6	12	72	8			8				
Holbrook	Rte 1	SB	1	6	12	72	8			8				
Holbrook	Rte 1	SB	1	6	6	36	4		4					
Holbrook	Rte 1	SB	1	6	6	36	4		4					
Holbrook	Rte 1	SB	1	6	15	90	10			10				
Holbrook	Rte 1	SB	1	6	12	72	8			8				
Holbrook	Rte 1	SB	1	6	12	72	8			8				
Rte 1	Holbrook	NB	1	6	12	72	8			8				
Rte 1	Holbrook	NB	1	6	12	72	8			8				
Rte 1	Holbrook	NB	1	6	12	72	8			8				
Rte 1	Holbrook	NB	1	6	12	72	8			8				
Rte 1	Holbrook	NB	1	12	24	288	32					32		
Rte 1	Holbrook	NB	1	6	6	36	4		4					
Rte 1	Holbrook	NB	1	6	6	36	4		4					
Rte 1	Holbrook	NB	1	12	30	360	40	40						

Total 222 40 36 114 0 32 200 10
SY SY SY SY SY SY FT EACH

FILE NAME =	USER NAME = wlgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE GLENWOOD DYER RD.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\projects\136788\design.es.dgn		DRAWN -	REVISED -			VAR.	2008-016 PP	COOK	131	46
	PLOT SCALE = 1/8" = 100'	CHECKED -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		CONTRACT NO. 60E42		
	PLOT DATE = 3/15/2008	DATE -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.						