ROUTE: Kean Ave (111th St to 95th St)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
95th	107th	SB	1	12	20	240	27					27		
95th	107th	SB	1	6	20	120	13			13				
95th	107th	SB	1	12	6	72	8			8				
95th	107th	SB	1	12	6	72	8			8				
95th	107th	SB	1	12	6	72	8			8				
95th	107th	SB	1	12	50	600	67	67						
95th	107th	SB	1	6	100	600	67	67						
95th	107th	SB	1	1.5	50	75	8			8				
95th	107th	SB	1	12	10	120	13			13				
95th	107th	SB	1	6	15	90	10			10				
95th	107th	SB	1	6	15	90	10			10				
95th	107th	SB	1	12	20	240	27					27		
95th	107th	SB	1	6	100	600	67	67						
95th	107th	SB	1	6	75	450	50	50						
95th	107th	SB	1	6	50	300	33					33		
95th	107th	SB	1	6	8	48	5		5					
95th	107th	SB	1	12	20	240	27					27		
95th	107th	SB	1	12	10	120	13			13				
103rd	107th	SB	2	12	10	120	13			13				
103rd	107th	SB	2	12	50	600	67	67						
107th	111th	SB	1	12	8	96	11			11				
107th	111th	SB	1	6	80	480	53	53						
107th	111th	SB	1	6	80	480	53	53						
107th	111th	SB	1	6	80	480	53	53						
107th	111th	SB	1	6	250	1500	167	167						
107th	111th	SB	1	12	40	480	53	53						
107th	111th	SB	1	6	20	120	13			13				
107th	111th	SB	1	12	75	900	100	100						
		Total					3422 SY	2676 SY	5 SY	360 SY	33 SY	348 SY	11000 FT	50 EACH

65

FILE NAME = c:\projects\d136708\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE KEAN AVE.	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			VAR.	2008-016 PP	COOK	131 / 60
	PLOT SCALE = 103.7051 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60E42	
	PLOT DATE = 3/15/2008	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	