ROUTE: Main St (IL 171/Archer Ave to Illinois St)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
Illinois	Kotlin	EB	1	6	10	60	7			7				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	6	6	36	4		4					
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	6	15	90	10			10				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	30	360	40	40						
Illinois	Kotlin	EB	1	12	30	360	40	40						
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	6	20	120	13			13				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	6	72	8			8				
Illinois	Kotlin	EB	1	12	20	240	27					27		
Illinois	Kotlin	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	12	6	72	8			8				
Kotlin	Fransiscan Dr	EB	1	3	80	240	27					27		
Kotlin	Fransiscan Dr	EB	1	3	100	300	33					33		
Kotlin	Fransiscan Dr	EB	1	6	6	36	4		4					
Kotlin	Fransiscan Dr	EB	1	6	120	720	80	80						
Kotlin	Fransiscan Dr	EB	1	6	50	300	33					33		
Kotlin	Fransiscan Dr	EB	1	6	50	300	33					33		
Kotlin	Fransiscan Dr	EB	1	6	60	360	40	40						
Fransiscan Dr	Walker	EB	1	12	10	120	13			13				
Fransiscan Dr	Walker	EB	1	12	6	72	8			8				
Fransiscan Dr	Walker	EB	1	12	10	120	13			13				
Fransiscan Dr	Walker	EB	1	12	6	72	8			8				
Fransiscan Dr	Walker	EB	1	12	6	72	8			8				
Fransiscan Dr	Walker	EB	1	12	80	960	107	107						
Fransiscan Dr	Walker	EB	1	6	120	720	80	80						
Fransiscan Dr	Walker	EB	1	6	80	480	53	53						
Fransiscan Dr	Walker	EB	1	6	150	900	100	100						
Fransiscan Dr	Walker	EB	1	12	6	72	8			8				
Fransiscan Dr	Walker	EB	1	6	50	300	33					33		
Fransiscan Dr	Walker	EB	1	6	30	180	20				20			
Fransiscan Dr	Walker	EB	1	6	10	60	7			7				
Fransiscan Dr	Walker	EB	1	6	6	36	4		4					

CONTINUED ON THE NEXT SHEET

FILE NAME = c:\projects\d136788\design_aa.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.7051 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/15/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
MAIN ST.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-016 PP	COOK	131	68
		CONTRACT NO. 60E42		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT