ROUTE: Main St (IL 171/Archer Ave to Illinois St)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	MILL & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS
171	McGuire	WB	1	12	500	6000	667	667						
171	McGuire	WB	1	12	20	240	27					27		
171	McGuire	WB	1	6	100	600	67	67						
171	McGuire	WB	1	6	20	120	13			13				
171	McGuire	WB	1	12	8	96	11			11				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	20	240	27					27		
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	30	360	40	40						
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	8	96	11			11				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	6	6	36	4		4					
171	McGuire	WB	1	6	6	36	4		4					
171	McGuire	WB	1	6	10	60	7			7				
171	McGuire	WB	1	12	50	600	67	67						
171	McGuire	WB	1	12	50	600	67	67						
171	McGuire	WB	1	6	50	300	33					33		
171	McGuire	WB	1	12	8	96	11			11				
171	McGuire	WB	1	6	6	36	4		4					
171	McGuire	WB	1	6	6	36	4		4					
171	McGuire	WB	1	6	10	60	7			7				
171	McGuire	WB	1	12	50	600	67	67						
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
171	McGuire	WB	1	12	6	72	8			8				
McGuire	Walker	WB	1	12	6	72	8			8				
McGuire	Walker	WB	1	12	6	72	8			8				
McGuire	Walker	WB	1	12	12	144	16				16			
McGuire	Walker	WB	1	12	6	72	8			8				
McGuire	Walker	WB	1	12	6	72	8			8				
McGuire	Walker	WB	1	12	6	72	8			8				
Walker	Fransiscan Dr	WB	1	12	6	72	8			8				
Walker	Fransiscan Dr	WB	1	12	6	72	8			8				
Walker	Fransiscan Dr	WB	1	12	6	72	8			8				
Walker	Fransiscan Dr	WB	1	12	6	72	8			8				
Fransiscan Dr	Illinois	WB	1	6	20	120	13			13				
Fransiscan Dr	Illinois	WB	1	6	10	60	7			7				
Fransiscan Dr	Illinois	WB	1	6	10	60	7			7				
Fransiscan Dr	Illinois	WB	1	12	12	144	16				16			
Fransiscan Dr	Illinois	WB	1	12	6	72	8			8				
Fransiscan Dr	Illinois	WB	1	12	6	72	8			8				
Fransiscan Dr	Illinois	WB	1	12	6	72	8			8				
Fransiscan Dr	Illinois	WB	1	12	80	960	107	107						
Fransiscan Dr	Illinois	WB	1	12	50	600	67	67						
		Total					7252 SY	4849 SY	36 SY	1367 SY	299 SY	705 SY	34000 FT	430 EACH

FILE NAME = c:\projects\d136708\design.aa.dgn

USER NAME = wilgreendp | PLOT SCALE = 103.7051 ' / IN. | PLOT DATE = 3/15/2008

DESIGNED - | DRAWN - | CHECKED - | DATE -

REVISED - | REVISED - | REVISED - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
MAIN ST.

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2008-016 PP	COOK	131	71

CONTRACT NO. 60E42

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT