ROUTE: 26th St (East End to Western Ave)

CROSS	S STREETS	DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR	MILL	CLASS D	CLASS D	CLASS D	CLASS D	PAVT	RAISED
FROM	ТО	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA	&	PATCH	PATCH	PATCH	PATCH	MARKING	REFL
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	. (SQ FT)	(SQ YD)	RESURF	TYPE I	TYPE II	TYPE III	TYPE IV	4"	PAVT MKS
Western	Ashland	EB	1	12	40	480	53	53						
Western	Ashland	EB	1	12	50	600	67	67						
Western	Ashland	EB	1	12	50	600	67	67	" , "					
Western	Ashland	EB	1	6	30	180	20				20			
Western	Ashland	EB	1	6	6	36	4		4					
Western	Ashland	EB	1	6	50	300	33					33		
Western	Ashland	EB	1	6	200	1200	133	133						
Western	Ashland	EB	1	12	40	480	53	53						
Western	Ashland	EB	1	6	200	1200	133	133						·
Western	Ashland	EB	1	6	30	180	20				20			
Western	Ashland	EB	1	6	30	180	20				20			
Ashland	Chicago Rd	EB	1	6	12	72	8			8				
Ashland	Chicago Rd	EB	1	6	6	36	4		4					
Ashland	Chicago Rd	EB	1.	6	12	72	8			8				
Ashland	Chicago Rd	EB	1	12	20	240	27	,				27		
Ashland	Chicago Rd	EB	1	6	6	36	4		4					
Ashland	Chicago Rd	EB	1	6	12	72	8			8				
Chicago Rd	East End	EB	1	6	6	36	4		4					
Chicago Rd	East End	EB	1	12	12	144	16				16			
Chicago Rd	East End	EB	1	6	6	36	4		4					

Total 1,718 1,010 64 209 256 179 **4200 105** SY SY SY SY SY SY FT EACH

2

FILE NAME =	ประท NAME ะ พ.lgreendp	DESIGNED -	REVISED -	Ī
c:\projects\d136708\design_ee.dgn		DRAWN -	REVISED -	
	PLOT SCALE = 103.7051 '/ IN.	CHECKED -	REVISED -	
· ·	PLOT DATE = 3/15/2008	DATE -	REVISED -	L

STATE	01	FILLINOIS
DEPARTMENT	0F	TRANSPORTATION

PATCHING SCHEDULE 26TH ST.							SECTION	COUNTY	TOTAL	S N
							2008~016 PP	CODK	131	10
								CONTRAC	NO.	60E
SCALE:	SHEET N	0. OF	SHEETS	STA.	TO STA.	FED. R	DAD DIST. NO. 1 ILLINOIS FED. A	ID PROJECT		