

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1-3-K	ROCK ISLAND	476	50
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

# SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
6010060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH			
	MILAN BELTWAY				
	LT. STA. 361+00	1			
	RT. STA. 361+00	1			
	RT. STA. 364+05	1			
	LT. STA. 364+21	1			
	JOHN DEERE ROAD				
	RT. STA. 389+25	1			
	LT. STA. 392+25	1			
	LT. STA. 396+00	1			
	LT. STA. 400+00	1			
	RT. STA. 400+00	1			
	RT. STA. 404+00	1			
	LT. STA. 405+00	1			
	RT. STA. 408+00	1			
	RT. STA. 412+00	1			
	LT. STA. 414+70	1			
	RAMP 1				
	LT. STA. 4+00	1			
	LT. STA. 8+00	1			
	RT. STA. 9+00	1			
	RT. STA. 13+50	1			
	RAMP 2				
	LT. STA. 9+50	1			
	LT. STA. 12+50	1			
	RAMP 3				
	RT. STA. 6+50	1			
	RT. STA. 9+50	1			
	LT. STA. 13+50	1			
	RAMP 4				
	RT. STA. 4+50	1			
	RT. STA. 8+50	1			
	RT. STA. 11+50	1			
	TOTAL	26			
60100945	PIPE DRAINS 12"	FT.			
	MILAN BELTWAY				
	LT. STA. 356+91	46			
	RT. STA. 356+91	72			
	52ND AVENUE				
	LT. STA. 1157+93.5	78			
	RT. STA. 1160+75	75			
	LT. STA. 1160+75	75			
	RT. STA. 1163+00	94			
	LT. STA. 1163+25	81			
	RT. STA. 1164+72.5	92			
	LT. STA. 1165+50	68			
	LT. STA. 1167+50	66			
	RAMP 1				
	RT. STA. 1+37.50	78			
	VALLEY VIEW				
	RT. STA. 154+00	30			
	RT. STA. 155+50	38			
	RT. STA. 157+75	32			
	LT. STA. 160+15	34			
	RT. STA. 160+60	36			
	RT. STA. 161+50	76			
	LT. STA. 161+50	40			
	RT. STA. 163+25	38			
	LT. STA. 163+25	40			
	RT. STA. 165+00	26			
	LT. STA. 165+00	26			
	TOTAL	1,241			
60100955	PIPE DRAINS 15"	FT.			
	MILAN BELTWAY				
	RT. STA. 364+00	48			
	BLACKHAWK ROAD				
	LT. STA. 1154+00	76			
	TOTAL	124			
60107600	PIPE UNDERDRAINS 4"	FT.			
	MILAN BELTWAY				
	33.5' RT. STA. 357+13.7-33.5' RT. STA. 361+00	386			
	33.5' LT. STA. 357+13.7-33.5' LT. STA. 361+00	386			
	33.5' RT. STA. 361+00-33.5' RT. STA. 364+05	305			
	33.5' LT. STA. 361+00-33.5' LT. STA. 364+21	321			
	JOHN DEERE ROAD				
	33.5' RT. STA. 384+50.00' RT. STA. 389+25	475			
	33.5' LT. STA. 386+50-33.5' LT. STA. 389+25	275			
	33.5' RT. STA. 389+25-33.5' RT. STA. 392+00	275			
	33.5' LT. STA. 389+25-33.5' LT. STA. 392+25	300			
	33.5' LT. STA. 392+25-33.5' LT. STA. 396+00	375			
	33.5' LT. STA. 396+00-33.5' LT. STA. 400+00	400			
	47.5' RT. STA. 400+00-47.5' RT. STA. 404+00	400			
	33.5' LT. STA. 400+00-33.5' LT. STA. 405+00	500			
	47.5' RT. STA. 404+00-47.5' RT. STA. 408+00	400			
	33.5' LT. STA. 405+00-33.5' LT. STA. 410+00	500			
	47.5' RT. STA. 408+00-47.5' RT. STA. 412+00	400			
	47.5' RT. STA. 412+00-47.5' RT. STA. 415+45	345			
	47.5' LT. STA. 414+70-47.5' LT. STA. 417+10	260			
	RAMP 1				
	16' LT. STA. 1+00-16' LT. STA. 4+00	300			
	16' LT. STA. 4+00-16' LT. STA. 8+00	400			
	STA. 7+50-9+00	150			
	STA. 9+00-13+50	450			
	STA. 13+50-18+50	500			
	RAMP 2				
	24' LT. STA. 4+50-24' LT. STA. 9+50	500			
	24' LT. STA. 9+50-36' LT. STA. 12+50	300			
	36' LT. STA. 12+50-36' LT. STA. 15+50	300			
	RAMP 3				
	STA. 3+65-6+50	385			
	STA. 6+50-9+50	300			
	STA. 9+50-10.4' RT. STA. 13+50	400			
	16' LT. STA. 13+50-12' LT. STA. 17+30	380			
	RAMP 4				
	STA. 0+50-4+50	400			
	STA. 4+50-8+50	400			
	STA. 8+50-11+50	300			
	STA. 11+50-14+27	277			
	TOTAL	12,045			
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FT.			
	MILAN BELTWAY				
	33.5' RT. STA. 361+00	23			
	33.5' LT. STA. 361+00	23			
	33.5' RT. STA. 364+05	23			
	33.5' LT. STA. 364+21	34			
	JOHN DEERE ROAD				
	33.5' RT. STA. 389+25	22			
	33.5' LT. STA. 392+25 (2)	38			
	33.5' LT. STA. 396+00	16			
	47.5' RT. STA. 400+00	20			
	33.5' LT. STA. 400+00	32			
	47.5' RT. STA. 404+00	20			
	33.5' LT. STA. 405+00	20			
	47.5' RT. STA. 408+00	20			
	47.5' RT. STA. 412+00	20			
	47.5' LT. STA. 414+70	18			
	RAMP 1				
	LT. STA. 4+00	16			
	LT. STA. 8+00	16			
	RT. STA. 9+00 (2)	32			
	RT. STA. 13+50	16			
	RAMP 2				
	LT. STA. 9+50 (2)	48			
	LT. STA. 12+50	20			
	RAMP 3				
	RT. STA. 6+50	16			
	RT. STA. 9+50 (2)	32			
	LT. STA. 13+50	16			
	RAMP 4				
	RT. STA. 4+50	16			
	RT. STA. 8+50 (2)	32			
	RT. STA. 11+50	16			
	TOTAL	605			
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			
	MILAN BELTWAY				
	RT. STA. 364+00	1			
	52ND AVENUE				
	SANITARY SEWER				
	37.95' RT. STA. 4+65.55	1			
	28' RT. STA. 8+34.50	1			
	41.96' LT. STA. 1170+31.76	1			
	52.09' LT. STA. 1173+84.08	1			
	50.43' LT. STA. 211+31.19	1			
	34.51' LT. STA. 215+30.88	1			
	28.82' LT. STA. 217+71.97	1			
	18.56' LT. STA. 218+46.24	1			
	VALLEY VIEW				
	LT. STA. 1152+60	1			
	TOTAL	10			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			
	VALLEY VIEW				
	RT. STA. 152+28.12	1			
	RELOCATED THIRD STREET				
	LT. STA. 4+00	1			
	RT. STA. 7+50	1			
	TOTAL	3			
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH			
	RELOCATED THIRD STREET				
	RT. STA. 10+00	1			
	RT. STA. 11+43.15	1			
	TOTAL	2			
60240220	INLETS, TYPE B, TYPE 3 FRAME & GRATE	EACH			
	BLACKHAWK ROAD				
	LT. STA. 1148+65	1			
	LT. STA. 1149+80	1			
	LT. STA. 1152+67.50	1			
	RT. STA. 1152+75	1			
	RT. STA. 1154+20	1			
	LT. STA. 1154+20	1			
	52ND AVENUE				
	RT. STA. 1157+15	1			
	RT. STA. 1160+75	1			
	LT. STA. 1160+75	1			
	LT. STA. 1163+25	1			
	TOTAL	10			
60240310	INLETS, TYPE B, TYPE 11 FRAME & GRATE	EACH			
	BLACKHAWK ROAD				
	LT. STA. 1148+55	1			
	LT. STA. 1149+75	1			
	TOTAL	2			
60242700	INLETS SPECIAL, NO. 3	EACH			
	52ND AVENUE				
	RT. STA. 1171+75	1			
	RT. STA. 1173+00	1			
	RELOCATED THIRD STREET				
	LT. STA. 3+14.53	1			
	RT. STA. 5+00	1			
	LT. STA. 5+00	1			
	TOTAL	5			
60242801	INLETS SPECIAL, NO. 5	EACH			
	BLACKHAWK ROAD				
	RT. STA. 1142+72.4	1			
	RT. STA. 1144+16	1			
	RT. STA. 1146+25	1			
	RT. STA. 1147+10	1			
	RT. STA. 1147+85	1			
	RT. STA. 1148+50	1			
	LT. STA. 1148+80	1			
	LT. STA. 1150+00	1			
	RT. STA. 1150+25	1			
	RT. STA. 1151+75	1			
	RT. STA. 1152+50	1			
	LT. STA. 1153+00	1			
	RT. STA. 1154+00	1			
	LT. STA. 1154+00	1			